DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS		
INT.	DATA ENG.	REASON

CHECKS		
INT.	DATE	REASON

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
609	****	ST. CLAIR	350	32
STA. 26+00		TO STA. 56+00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

**** 76RS-3, 76-2BR-2I

N

0 50 100

SCALE IN FEET

STA. 26+00 MATCH LINE

STA. 41+00 MATCH LINE

℄ FAP 609 (IL RTE 163)

30+00 35+00 40+00

RELOCATE (BY OTHERS)

18" CMP TO BE REMOVED

RELOCATE (BY OTHERS)

RELOCATE (BY OTHERS)

PAVED SHOULDER REMOVAL 167 SQ. YD.

RELOCATE (BY OTHERS)

21" CMP TO BE REMOVED

RELOCATE (BY OTHERS)

24" CMP TO BE REMOVED

RELOCATE (BY OTHERS)

REL. (BY OTHERS)

TRIPLE 26' - 18"x24" CMP WITH RC HEADWALLS REMOVALL OF EXISTING STRUCTURE NO. 1

DRIVEWAY PAVEMENT REMOVAL 45 SQ. YD.

+05 F.E. EARTH

+30 P.E. AGG.

15" CMP TO BE REMOVED

PAVED SHOULDER REMOVAL 167 SQ. YD.

TREE REMOVAL 0.06 ACRE

RELOCATE (BY OTHERS)

BUSH

BRICK HEADWALLS

RELOCATE (BY OTHERS)

8" Conc.

18" TO BE REMOVED

+82 P.E. AGG. / BIT.

LEGEND

- PAVEMENT REMOVAL
- DRIVEWAY PAVEMENT REMOVAL
- PAVED SHOULDER REMOVAL
- TREE REMOVAL (ACRE)
- TREE REMOVAL (IN. DIA.)

N

0 50 100

SCALE IN FEET

STA. 41+00 MATCH LINE

STA. 56+00 MATCH LINE

℄ FAP 609 (IL RTE 163)

45+00 50+00 55+00

6' X 3' RCBC - 19 FOOT REMOVAL OF EXISTING STRUCTURE NO. 2

RELOCATE (BY OTHERS)

54" CMP - 103 FOOT REMOVAL OF EXISTING STRUCTURE NO. 2

TREE REMOVAL 0.25 ACRE

6'x5' CONC. ARCH. BOX - 30 FOOT REMOVAL OF EXISTING STRUCTURE NO. 3

RELOCATE (BY OTHERS)

15" CMP TO BE REMOVED

15" CMP TO BE REMOVED

PAVED SHOULDER REMOVAL 167 SQ. YD.

RELOCATE (BY OTHERS)

RELOCATE (BY OTHERS)

RELOCATE (BY OTHERS)

RELOCATE (BY OTHERS)

36" CMP TO BE REMOVED

12" CMP TO BE REMOVED

36" CMP TO BE REMOVED

PAVEMENT PATCHING, TYPE IV, 2 @ 25 SQ YD

18.83'

REMOVAL OF EXISTING RIPRAP 226 SQ YD

DRIVEWAY PAVEMENT REMOVAL 100 SQ. YD.

RELOCATE (BY OTHERS)

TREE REMOVAL 0.13 ACRE

15" CMP TO BE REMOVED

DRIVEWAY PAVEMENT REMOVAL 73 SQ. YD.

SCHRANZ LANE (PRIVATE)

PAVED SHOULDER REMOVAL 167 SQ. YD.

15" CONC. TO BE REMOVED

36" CMP TO BE REMOVED

EXISTING LIGHTING TO REMAIN

REVISIONS	
NAME	DATE
IDOT REVIEW	MAR/08
IDOT REVIEW	09/08

ILLINOIS DEPARTMENT OF TRANSPORTATION

REMOVAL & ADJUSTMENT PLANS

FAP 609 (ILLINOIS ROUTE 163)
SECTION 76RS-3, 76-2BR-2I
ST. CLAIR COUNTY

SCALE: VERT.
HORIZ.
DATE: 11/22/02

DRAWN BY: VERENSKI
DESIGNED BY: BOTT
CHECKED BY: EMRICK

GREENE & BRADFORD, INC. OF SPRINGFIELD

COMPUTER FILE NO. ROADREMOVAL03

PROJECT 02076 6/22/07-MDS

IDOTPL-50 1"=50' 8/07/00

REMOVAL & ADJUSTMENT - FAP 609 (IL RTE. 163) ST. CLAIR COUNTY

STA. 26+00 TO STA. 56+00