


F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
609	***	ST. CLAIR	350	42
STA. 56+00		TO STA. 71+00		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*** 76RS-3, 76-2BR-21				



PAUL H. BECKER & DEBORAH D. HAMILTON

HUGO & CECILIA ROHR

ERWIN SCHARF

LESLIE W. HUWER ESTATE

BRUCE K. & SANDRA K. SIDDLE

LEROY & WANDA D. SCHARF

DARRELL W. & MARIA J. SCHARF

STA. 60+46.94
PIPE CULVERTS, CLASS A, TYPE 2 54"
- 78' FOOT @ 4.15% SLOPE
(2) PRECAST REINFORCED CONCRETE
FLARED END SECTIONS 54" WITH GRATING
USFL = 576.30 (60+43, 40.5' RT.)
DSFL = 572.40 (60+52, 53.5' LT.)
TRENCH BACKFILL = 89 C.Y.

STA. 62+72, 28' LT.
PIPE CULVERTS, CLASS D,
TYPE 1 15" = 30 FOOT
USFL = 584.65
DSFL = 584.13
TRENCH BACKFILL = 2 C.Y.

STA. 63+93, 28.5' LT.
PIPE CULVERTS, CLASS D,
TYPE 1 15" = 32 FOOT
USFL = 586.19
DSFL = 585.89
TRENCH BACKFILL = 2 C.Y.

STA. 59+28, 30' LT.
PIPE CULVERTS, CLASS D,
TYPE 1 15" = 34 FOOT
USFL = 582.93
DSFL = 582.73
TRENCH BACKFILL = 2 C.Y.

STA. 59+30, 28.5' RT.
PIPE CULVERTS, CLASS D,
TYPE 1 18" = 34 FOOT
USFL = 583.19
DSFL = 583.02
TRENCH BACKFILL = 3 C.Y.

STA. 62+28, 28.75' RT.
PIPE CULVERTS, CLASS A,
TYPE 1 18" = 34 FOOT
PRECAST REINFORCED CONCRETE
FLARED END SECTIONS 18" = 2 EA.
USFL = 584.44 (27.0 RT.)
DSFL = 583.09 (30.5 RT.)
TRENCH BACKFILL = 4 C.Y.

STA. 63+09, 27' RT.
PIPE CULVERTS, CLASS A,
TYPE 1 18" = 20 FOOT
PRECAST REINFORCED CONCRETE
FLARED END SECTIONS 18" = 2 EA.
USFL = 585.46
DSFL = 584.91
TRENCH BACKFILL = 2 C.Y.

STA. 64+13, 27' RT.
PIPE CULVERTS, CLASS A,
TYPE 1 18" = 20 FOOT
PRECAST REINFORCED CONCRETE
FLARED END SECTIONS 18" = 2 EA.
USFL = 586.81
DSFL = 586.41
TRENCH BACKFILL = 2 C.Y.

BM # 6
STA. 59+77, 42' LT.
SMALL SPIKE IN WEST FACE P.P.
ELEV. 586.20

BM # 7
STA. 70+64, 52' RT.
SMALL SPIKE IN WEST FACE P.P.
ELEV. 596.08

REVISION	DATE	BY
100% REVIEW	3/17/08	WCB/MDS

GREENE & BRADFORD, INC.
OF SPRINGFIELD
ENGINEERS & ARCHITECTS
1000 W. WASHINGTON ST., SUITE 200
SPRINGFIELD, ILLINOIS 62760
TEL: 217-223-1234 FAX: 217-223-1235
WWW.GREENE-AND-BRADFORD.COM

COMPUTER FILE NO. PLN163B_V8-03
PROJECT: 02076
01/03/08-MDS

DESIGN	INT.	DATE	REASON

PLAN	REVISION	DATE	BY

PROFILE	REVISION	DATE	BY

CHECKS	INT.	DATE	REASON

