

DESIGN INT. DATE REASON

F.A.P. SECTION COUNTY TOTAL SHEETS SHEET NO. 609 ... ST. CLAIR 350 55

PLOTS & CHECKS INT. DATE NO. REASON

CHECKS INT. DATE REASON

20200100 EARTH EXCAVATION CU YD LOCATION 4782 84 + 00 - 99 + 00 ILLINOIS ROUTE 163 STAGE 1

31000600 PROCESSING LIME STABILIZED SOIL MIXTURE 12" SQ YD LOCATION 1920 87 + 25 - 93 + 70 ILLINOIS ROUTE 163 STAGE 2

31001500 LIME TON LOCATION 44 87 + 25 - 93 + 70 ILLINOIS ROUTE 163 STAGE 2

31100100 SUB-BASE GRANULAR MATERIAL, TYPE A TON LOCATION 155 93 + 70 - 94 + 30 ILLINOIS ROUTE 163 STAGE 2B

35101400 AGGREGATE BASE COURSE, TYPE B TON LOCATION 23 90 + 75 - LT. PE ALONG ILLINOIS RTE. 163 STAGE 2

40200800 AGGREGATE SURFACE COURSE, TYPE B TON LOCATION 15 98 + 45 - RT. PE ALONG ILLINOIS RTE. 163 STAGE 1

40600200 BITUMINOUS MATERIALS (PRIME COAT) TON LOCATION 0.3 93 + 70 - 94 + 30 ILLINOIS ROUTE 163 STAGE 2

40600635 LEVELING BINDER (MACHINE METHOD), N70 TON LOCATION 96 87 + 25 - 95 + 65 ILLINOIS ROUTE 163 STAGE 2

40603315 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70 TON LOCATION 431 11 + 66 - 24 + 39 IL RTE. 163 - RUN AROUND STAGE 2

40603085 HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70 TON LOCATION 1641 11 + 66 - 24 + 39 IL RTE. 163 - RUN AROUND STAGE 1

40800020 BITUMINOUS MATERIALS (PRIME COAT) TON LOCATION 0.1 19 + 60 - 20 + 30 IL RTE. 163 - RUN AROUND STAGE 1

40800050 INCIDENTAL HOT-MIX ASPHALT SURFACING TON LOCATION 8 90 + 75 - LT. PE ALONG ILLINOIS RTE. 163 STAGE 2

44000100 PAVEMENT REMOVAL SQ YD LOCATION 1864 87 + 25 - 93 + 70 ILLINOIS ROUTE 163 STAGE 2A

402004250 PAVED SHOULDER REMOVAL SQ YD LOCATION 171 89 + 94, LT. - 93 + 28, LT. ILLINOIS ROUTE 163 STAGE 2

48101200 AGGREGATE SHOULDERS, TYPE B TON LOCATION 88 10 + 00, RT. - 19 + 28, RT. IL RTE. 163 - RUN AROUND STAGE 1

48203029 HOT-MIX ASPHALT SHOULDERS, 8" SQ YD LOCATION 405 84 + 00, LT. - 93 + 10, LT. ILLINOIS ROUTE 163 STAGE 2

542A0220 PIPE CULVERTS, CLASS A, TYPE 1 15" FOOT LOCATION 98 93 + 34 - 34' LT. ILLINOIS ROUTE 163 STAGE 1

5422D015 PIPE CULVERTS, CLASS D, TYPE 2 15" (TEMPORARY) FOOT LOCATION 64 2 + 25 - 0' RT. ZINGG ROAD STAGE 1

54213660 PRECAST REINFORCED CONCRETE FLARED END SECTION 15" EACH LOCATION 1 93 + 16 - 34' LT. ILLINOIS ROUTE 163 STAGE 1

60219000 MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE EACH LOCATION 1 2 + 38 - 18' RT. ZINGG ROAD - RUN AROUND STAGE 1

60236200 INLETS, TYPE A, TYPE 8 GRATE EACH LOCATION 1 2 + 00 - 18' LT. MINE HAUL RD-RUN AROUND STAGE 1

ILLINOIS DEPARTMENT OF TRANSPORTATION STAGING QUANTITY SCHEDULE FAP 609 (IL RTE. 163) SECTION 76RS-3, 76-2BR-21 ST. CLAIR COUNTY

REVISIONS NAME DATE