

DESIGN		
INT.	DATE	REASON

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
609	***	ST. CLAIR	350	56
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
***76RS-3, 76-2BR-21				

70300100 SHORT-TERM PAVEMENT MARKING

FOOT	LOCATION				
210	87 + 25	-	95 + 65	ILLINOIS ROUTE 163	STAGE 2
30	498 + 50	-	499 + 70	ZINGG ROAD	STAGE 2
55	500 + 30	-	502 + 50	MINE HAUL ROAD	STAGE 2
295	TOTAL				

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

FOOT	LOCATION				
3154	10 + 00	-	25 + 77	ILLINOIS ROUTE 163 - DY	STAGE 1
1010	10 + 00, LT.	-	20 + 10, LT.	ILLINOIS ROUTE 163 - W ED	STAGE 1
930	10 + 00, RT.	-	19 + 30, RT.	ILLINOIS ROUTE 163 - W ED	STAGE 1
567	20 + 10, RT.	-	25 + 77, RT.	ILLINOIS ROUTE 163 - W ED	STAGE 1
482	20 + 95, LT.	-	25 + 77, LT.	ILLINOIS ROUTE 163 - W ED	STAGE 1
485	0 + 24, LT.	-	4 + 43, LT.	ZINGG ROAD - W EDGE	STAGE 1
860	0 + 00	-	4 + 30	ZINGG ROAD - DY	STAGE 1
433	0 + 28, RT.	-	4 + 43, RT.	ZINGG ROAD - W EDGE	STAGE 1
470	0 + 05, LT.	-	4 + 65, LT.	MINE HAUL ROAD - W EDGE	STAGE 1
445	0 + 23	-	4 + 30	MINE HAUL ROAD - DY	STAGE 1
469	0 + 20, RT.	-	4 + 65, RT.	MINE HAUL ROAD - W EDGE	STAGE 1
9305	TOTAL				

70300280 TEMPORARY PAINT PAVEMENT MARKING - LINE 24"

FOOT	LOCATION				
16	4 + 30	-	RT.	ZINGG ROAD RUNAROUND	STAGE 1
14	0 + 23	-	LT.	MINE HAUL RD. RUNAROUND	STAGE 1
44	TOTAL				

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION				
98	10 + 00	-	11 + 48	ILLINOIS ROUTE 163 - DY	STAGE 2
100	10 + 00, LT.	-	13 + 00, LT.	ILLINOIS ROUTE 163 - W ED	STAGE 2
81	24 + 56	-	25 + 77	ILLINOIS ROUTE 163 - DY	STAGE 2
90	23 + 04, LT.	-	25 + 77, LT.	ILLINOIS ROUTE 163 - W ED	STAGE 2
55	0 + 00	-	0 + 83	ZINGG ROAD - DY	STAGE 2
52	0 + 28, RT.	-	1 + 83, RT.	ZINGG ROAD - W EDGE	STAGE 2
60	2 + 87, LT.	-	4 + 66, LT.	MINE HAUL ROAD - W EDGE	STAGE 2
67	3 + 67	-	4 + 68	MINE HAUL ROAD - DY	STAGE 2
603	TOTAL				

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION				
675	86 + 50, RT.	-	93 + 25, RT.	ILLINOIS ROUTE 163	STAGE 1
175	94 + 74, RT.	-	96 + 49, RT.	ILLINOIS ROUTE 163	STAGE 1
850	TOTAL				

78300100 PAVEMENT MARKING REMOVAL

SQ FT	LOCATION				
7	83 + 52	-	83 + 70	ILL. RTE. 163 - DOUBLE Y	STAGE 1
55	83 + 70, RT.	-	85 + 00, RT.	ILL. RTE. 163 - SINGLE Y	STAGE 1
14	83 + 70, LT.	-	85 + 00, LT.	ILL. RTE. 163 - SKIP DASH Y	STAGE 1
138	83 + 52, RT.	-	86 + 80, RT.	ILL. RTE. 163 - EDGE LINE W	STAGE 1
50	93 + 70	-	94 + 30	ILL. RTE. 163 - BOTH EDGE W	STAGE 1
50	93 + 70	-	94 + 30	ILL. RTE. 163 - DOUBLE Y	STAGE 1
126	96 + 20, RT.	-	99 + 20, RT.	ILL. RTE. 163 - EDGE LINE W	STAGE 1
104	98 + 00	-	99 + 22	ILL. RTE. 163 - DOUBLE Y	STAGE 1
544	TOTAL				

Z0030280 IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3

EACH	LOCATION				
1	86 + 50			ILLINOIS ROUTE 163	STAGE 1
1	96 + 49			ILLINOIS ROUTE 163	STAGE 1
2	TOTAL				

PLOTS & CHECKS		
INT.	DATE	REASON

CHECKS		
INT.	DATE	REASON

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
STAGING QUANTITY SCHEDULES
 FAP 609 (IL RTE. 163)
 SECTION 76RS-3, 76-2BR-21
 ST. CLAIR COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE: 7/18/08

DRAWN BY: SUTHEARD
 DESIGNED BY: BOTT
 CHECKED BY: SUTHEARD

GREENE & BRADFORD, INC.
 OF SPRINGFIELD
 CONSULTING ENGINEERS
 500 COMMERCIAL DRIVE
 SPRINGFIELD, ILLINOIS 62761
 1-217-752-8844

COMPUTER FILE NO.
 PLNSTGSUM.dgn
 PROJECT: 02076
 DATE - INIT