

MODEL: SOQ [Sheet] - 1
FILE NAME: c:\p\work\pwt\all\jetteam\1100554\1468box-sh1-SOQ.dgn

** STATE FUNDS ONLY

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
				ROADWAY	BOX CULVERT	BOX CULVERT
				0005	0004	0004
				RURAL	SN 094-2018	SN 094-2017
20100500	TREE REMOVAL, ACRES	ACRE	10	10	0	0
20200100	EARTH EXCAVATION	CU YD	140120	140120	0	0
20700220	POROUS GRANULAR EMBANKMENT	CU YD	4305	1790	1198	1317
20800150	TRENCH BACKFILL	CU YD	768	768	0	0
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	72479	71909	285	285
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	151220	151220	0	0
25000210	SEEDING, CLASS 2A	ACRE	44.25	44.25	0	0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3963	3963	0	0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3963	3963	0	0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3963	3963	0	0
25000750	MOWING	ACRE	264.25	264.25	0	0
25100115	MULCH, METHOD 2	ACRE	44.25	44.25	0	0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	4403	4403	0	0
28000305	TEMPORARY DITCH CHECKS	FOOT	5028	5028	0	0

USER NAME = alex.jette	DESIGNED -	REVISED -
	DRAWN -	REVISED -
	CHECKED -	REVISED -
PLOT DATE = 8/11/2025	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 8 OF 13 SHEETS STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310		WARREN	277	8
CONTRACT NO. 68B60				
ILLINOIS FED. AID PROJECT				

MODEL: SOQ (Sheet) - 10 - Copy-12 - Copy-1
FILE NAME: c:\pwworking\jetteam\1100554\1468box-sh1-SOQ.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
				ROADWAY	BOX CULVERT	BOX CULVERT
				0005	0004	0004
				RURAL	SN 094-2018	SN 094-2017
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	34290	34290	0	0
X0327423	CONNECTION TO EXISTING CULVERT	EACH	1	1	0	0
X2511630	EROSION CONTROL BLANKET (SPECIAL)	SQ YD	43339	43339	0	0
X4400196	HOT-MIX ASPHALT SURFACE REMOVAL (SPECIAL)	SQ YD	5086	5086	0	0
X4402720	GUTTER REMOVAL (SPECIAL)	FOOT	7530	7530	0	0
X4421000	PARTIAL DEPTH PATCHING	TON	3978	3978	0	0
X4421002	PARTIAL DEPTH PATCHING (SPECIAL)	SQ YD	17757	17757	0	0
X5400005	BOX CULVERT REMOVAL	FOOT	306	306	0	0
X6050040	REMOVING MANHOLES (SPECIAL)	EACH	4	4	0	0
X6050209	FILLING EXISTING CULVERTS	EACH	4	4	0	0
X6060097	CLASS SI CONCRETE (OUTLET), SPECIAL	CU YD	217	217	0	0
X6060101	CLASS SI CONCRETE PIPE UNDER DRAIN OUTLET	CU YD	14.5	14.5	0	0
X6062700	CONCRETE GUTTER, TYPE A (SPECIAL)	FOOT	8817	8817	0	0
X6350204	LINEAR DELINEATOR PANELS, 4 INCH	EACH	16	16	0	0

* SPECIALTY ITEM

USER NAME = alex.jette		DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -						310		WARREN	277	19
		CHECKED -	REVISED -		CONTRACT NO. 68B60								
PLOT DATE = 8/11/2025		DATE -	REVISED -		SCALE:	SHEET 19	OF 13 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			