

SCHEDULE OF QUANTITIES

LOCATION NO	1	STATE I.D. NO	1M0455031L000.0-000			
COUNTY	KANE	ROUTE	IL 31	M.P.:	0	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
SIGN PANEL - TYPE 1						SO FT 61
OVERHEAD SIGN STRUCTURE-MONOTUBE						FOOT 67
REMOVE OVERHEAD SIGN STRUCTURE, MONOTUBE-SPAN						EACH 1
REBUILD CONCRETE FOUNDATION FOR OVERHEAD SIGN STRUCTURE						EACH 2
TEMPORARY INFORMATION SIGNING						SO FT 35
TEMPORARY INFORMATION SIGNING - MOT						SO FT 26

LOCATION NO	2	STATE I.D. NO	1S049U012R000.0-000			
COUNTY	LAKE	ROUTE	US 12	M.P.:	0	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
OVERHEAD SIGN STRUCTURE-SPAN, TYPE I-A (4'-0" x 4'-6")						FOOT 73
REMOVE OVERHEAD SIGN STRUCTURE-SPAN						EACH 1
TEMPORARY INFORMATION SIGNING - MOT						SO FT 26
REMOVE AND REINSTALL SIGN PANEL						SO FT 206

LOCATION NO	3	STATE I.D. NO	1C049U041L000.0-001			
COUNTY	LAKE	ROUTE	DEERFIELD RD	M.P.:	0	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
SIGN PANEL - TYPE 3						SO FT 368
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE III-C-A (36" x 7'-0")						FOOT 35
DRILLED SHAFT CONCRETE FOUNDATIONS						CU YD 10.4
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER						EACH 1
REMOVE CONCRETE FOUNDATION-OVERHEAD						EACH 1
TEMPORARY INFORMATION SIGNING - MOT						SO FT 26

LOCATION NO	4	STATE I.D. NO	1C049U041R000.0-000			
COUNTY	LAKE	ROUTE	DEERFIELD RD	M.P.:	0	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
SIGN PANEL - TYPE 3						SO FT 200
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE III-C-A (36" x 7'-0")						FOOT 30
DRILLED SHAFT CONCRETE FOUNDATIONS						CU YD 9.0
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER						EACH 1
REMOVE CONCRETE FOUNDATION-OVERHEAD						EACH 1
TEMPORARY INFORMATION SIGNING - MOT						SO FT 26

LOCATION NO	5	STATE I.D. NO	1C045S056R000.0-000			
COUNTY	KANE	ROUTE	IL 56	M.P.:	0	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
SIGN PANEL - TYPE 3						SO FT 104
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE III-C-A (36" x 7'-0")						FOOT 35
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER						EACH 1
REBUILD CONCRETE FOUNDATION FOR OVERHEAD SIGN STRUCTURE						EACH 1
TEMPORARY INFORMATION SIGNING						SO FT 29
TEMPORARY INFORMATION SIGNING - MOT						SO FT 26

LOCATION NO	6	STATE I.D. NO	1B045S056L000.0-000			
COUNTY	KANE	ROUTE	IL 56	M.P.:	0	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
SIGN PANEL - TYPE 3						SO FT 190
OVERHEAD SIGN STRUCTURE-BRIDGE MOUNTED						FOOT 19
REMOVE OVERHEAD SIGN STRUCTURE-BRIDGE MOUNTED						EACH 1
TEMPORARY INFORMATION SIGNING						SO FT 55
TEMPORARY INFORMATION SIGNING - MOT						SO FT 26

LOCATION NO	8	STATE I.D. NO	1C022S038R000.0-001			
COUNTY	DuPAGE	ROUTE	YORK RD	M.P.:	0	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
SIGN PANEL - TYPE 3						SO FT 176
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE III-C-A (36" x 7'-0")						FOOT 35
DRILLED SHAFT CONCRETE FOUNDATIONS						CU YD 9.2
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER						EACH 1
REMOVE CONCRETE FOUNDATION-OVERHEAD						EACH 1
TEMPORARY INFORMATION SIGNING - MOT						SO FT 26

LOCATION NO	9	STATE I.D. NO	1C0161090R081.9-000			
COUNTY	COOK	ROUTE	1-90	M.P.:	81.9	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE II-C-A (36" x 5'-6")						FOOT 28
DRILLED SHAFT CONCRETE FOUNDATIONS						CU YD 7.1
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER						EACH 1
REMOVE CONCRETE FOUNDATION-OVERHEAD						EACH 1
REMOVE AND REINSTALL SIGN PANEL						SO FT 132

LOCATION NO	10	STATE I.D. NO	1C0161090R082.5-000			
COUNTY	COOK	ROUTE	1-90	M.P.:	82.5	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE II-C-A (36" x 5'-6")						FOOT 27
DRILLED SHAFT CONCRETE FOUNDATIONS						CU YD 7.1
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER						EACH 1
REMOVE CONCRETE FOUNDATION-OVERHEAD						EACH 1
REMOVE AND REINSTALL SIGN PANEL						SO FT 140

LOCATION NO	11	STATE I.D. NO	1C0161090R083.9-000			
COUNTY	COOK	ROUTE	1-90	M.P.:	83.9	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE II-C-A (36" x 5'-6")						FOOT 23
DRILLED SHAFT CONCRETE FOUNDATIONS						CU YD 7.1
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER						EACH 1
REMOVE CONCRETE FOUNDATION-OVERHEAD						EACH 1
REMOVE AND REINSTALL SIGN PANEL						SO FT 164

LOCATION NO	12	STATE I.D. NO	1S0161090L082.6-000			
COUNTY	COOK	ROUTE	1-90	M.P.:	82.6	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
OVERHEAD SIGN STRUCTURE-SPAN, TYPE I-A (4'-0" x 4'-6")						FOOT 67
REMOVE OVERHEAD SIGN STRUCTURE-SPAN						EACH 1
TEMPORARY INFORMATION SIGNING						SO FT 69
REMOVE AND REINSTALL SIGN PANEL						SO FT 447
REBUILD CONCRETE FOUNDATION FOR OVERHEAD SIGN STRUCTURE						EACH 2

LOCATION NO	13	STATE I.D. NO	1S045S056L000.0-000			
COUNTY	KANE	ROUTE	IL 56	M.P.:	0	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
REPLACE U-BOLT						EACH 2

LOCATION NO	14	STATE I.D. NO	1C049S043L000.0-000			
COUNTY	LAKE	ROUTE	IL 43	M.P.:	0	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
FIBER WRAP						SO FT 30

LOCATION NO	15	STATE I.D. NO	1S0161090L081.8-000			
COUNTY	COOK	ROUTE	1-90	M.P.:	81.8	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
OVERHEAD SIGN STRUCTURE-END CAP						EACH 3

LOCATION NO	16	STATE I.D. NO	1S0161090L079.9-000			
COUNTY	COOK	ROUTE	1-90	M.P.:	79.9	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
OVERHEAD SIGN STRUCTURE-END CAP						EACH 1

LOCATION NO	17	STATE I.D. NO	1C016U045R000.0-003			
COUNTY	COOK	ROUTE	US 45	M.P.:	0	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
METAL SCREEN						EACH 1

LOCATION NO	18	STATE I.D. NO	1S0161055L290.2-000			
COUNTY	COOK	ROUTE	IL 55	M.P.:	290.2	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
METAL SCREEN						EACH 1

LOCATION NO	19	STATE I.D. NO	1C022S083L000.0-003			
COUNTY	DuPAGE	ROUTE	IL 83	M.P.:		DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
TEMPORARY FENCE						FOOT 30
COMBINATION CURB AND GUTTER REMOVAL						FOOT 246
AGGREGATE SHOULDERS, TYPE B 10"						SO YD 82
CATCH BASINS TO BE ADJUSTED						EACH 1
CONCRETE CURB, TYPE B						FOOT 30
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24						FOOT 150
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (VARIABLE WIDTH CUTTER FLAG)						FOOT 86
TRAFFIC BARRIER TERMINAL, TYPE 6						EACH 4
TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT						EACH 2
GUARDRAIL REMOVAL						FOOT 91
SIGN PANEL - TYPE 3						SO FT 392
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE III-C-A (36" x 7'-0")						FOOT 33.5
DRILLED SHAFT CONCRETE FOUNDATIONS						CU YD 19.0
CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED						FOOT 96

LOCATION NO	15	STATE I.D. NO	1S0161090L081.8-000			
COUNTY	COOK	ROUTE	1-90	M.P.:	81.8	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
OVERHEAD SIGN STRUCTURE-END CAP						EACH 3

LOCATION NO	16	STATE I.D. NO	1S0161090L079.9-000			
COUNTY	COOK	ROUTE	1-90	M.P.:	79.9	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
OVERHEAD SIGN STRUCTURE-END CAP						EACH 1

LOCATION NO	17	STATE I.D. NO	1C016U045R000.0-003			
COUNTY	COOK	ROUTE	US 45	M.P.:	0	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
METAL SCREEN						EACH 1

LOCATION NO	18	STATE I.D. NO	1S0161055L290.2-000			
COUNTY	COOK	ROUTE	IL 55	M.P.:	290.2	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
METAL SCREEN						EACH 1

LOCATION NO	19	STATE I.D. NO	1C022S083L000.0-003			
COUNTY	DuPAGE	ROUTE	IL 83	M.P.:		DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
TEMPORARY FENCE						FOOT 30
COMBINATION CURB AND GUTTER REMOVAL						FOOT 246
AGGREGATE SHOULDERS, TYPE B 10"						SO YD 82
CATCH BASINS TO BE ADJUSTED						EACH 1
CONCRETE CURB, TYPE B						FOOT 30
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24						FOOT 150
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (VARIABLE WIDTH CUTTER FLAG)						FOOT 86
TRAFFIC BARRIER TERMINAL, TYPE 6						EACH 4
TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT						EACH 2
GUARDRAIL REMOVAL						FOOT 91
SIGN PANEL - TYPE 3						SO FT 392
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE III-C-A (36" x 7'-0")						FOOT 33.5
DRILLED SHAFT CONCRETE FOUNDATIONS						CU YD 19.0
CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED						FOOT 96

LOCATION NO	15	STATE I.D. NO	1S0161090L081.8-000			
COUNTY	COOK	ROUTE	1-90	M.P.:	81.8	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
OVERHEAD SIGN STRUCTURE-END CAP						EACH 3

LOCATION NO	16	STATE I.D. NO	1S0161090L079.9-000			
COUNTY	COOK	ROUTE	1-90	M.P.:	79.9	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
OVERHEAD SIGN STRUCTURE-END CAP						EACH 1

LOCATION NO	17	STATE I.D. NO	1C016U045R000.0-003			
COUNTY	COOK	ROUTE	US 45	M.P.:	0	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
METAL SCREEN						EACH 1

LOCATION NO	18	STATE I.D. NO	1S0161055L290.2-000			
COUNTY	COOK	ROUTE	IL 55	M.P.:	290.2	DIRECTION:
DESCRIPTION OF WORK						UNIT QUANTITY
METAL SCREEN						EACH 1

LOCATION NO	19	STATE I.D. NO	1C022S083L000.0-003			
COUNTY	DuPAGE	ROUTE	IL 83	M.P.:		