

EARTHWORK SCHEDULE

COMED ACCESS ROAD					
LOCATION		EARTH EXCAVATION (CUT)	EXCAVATION TO BE USED IN EMBANKMENT (CUT) *	EMBANKMENT (FILL)	EARTHWORK BALANCE, WASTE(+) OR SHORTAGE(-)
FROM	TO	CU. YD.	CU. YD.	CU. YD.	CU. YD.
300+00.00	300+50.00	41.0	34.9	0.0	34.9
300+50.00	301+00.00	44.0	37.4	22.4	15.0
301+00.00	301+50.00	55.9	47.5	74.5	-27.0
301+50.00	302+00.00	58.7	49.9	106.7	-56.8
302+00.00	302+50.00	91.9	78.1	116.7	-38.6
302+50.00	303+00.00	129.4	109.9	110.9	-1.0
303+00.00	303+50.00	147.5	125.4	108.2	17.1
303+50.00	304+00.00	148.1	125.8	103.7	22.1
304+00.00	304+50.00	160.5	136.4	86.9	49.5
304+50.00	305+00.00	90.9	77.3	82.1	-4.8
305+00.00	305+50.00	0.6	0.5	95.0	-94.5
305+50.00	306+00.00	0.6	0.5	107.0	-106.6
306+00.00	306+50.00	0.6	0.5	90.4	-89.9
306+50.00	307+00.00	0.6	0.6	57.2	-56.7
307+00.00	307+50.00	0.8	0.7	25.6	-24.8
307+50.00	308+00.00	2.8	2.4	11.0	-8.7
308+00.00	308+50.00	12.4	10.5	6.0	4.5
308+50.00	309+00.00	23.0	19.5	3.9	15.6
309+00.00	309+50.00	26.3	22.4	3.3	19.0
309+50.00	310+00.00	23.8	20.2	3.3	16.9
310+00.00	310+50.00	21.9	18.7	2.8	15.9
310+50.00	311+00.00	23.6	20.1	2.1	17.9
311+00.00	311+50.00	29.8	25.3	1.1	24.2
311+50.00	312+00.00	38.5	32.7	0.0	32.7
312+00.00	312+50.00	29.4	25.0	1.8	23.3
312+50.00	313+00.00	9.0	7.6	30.8	-23.2
313+00.00	313+50.00	0.6	0.5	100.6	-100.2
313+50.00	314+00.00	0.6	0.5	184.0	-183.5
314+00.00	314+50.00	0.6	0.5	264.2	-263.7
314+50.00	315+00.00	0.3	0.2	237.2	-237.0
315+00.00	315+50.00	0.0	0.0	0.0	0.0
315+50.00	316+00.00	0.4	0.3	240.4	-240.1
316+00.00	316+50.00	0.6	0.6	243.2	-242.7
316+50.00	317+00.00	0.6	0.5	125.4	-124.9
317+00.00	317+50.00	1.5	1.3	42.5	-41.2
317+50.00	318+00.00	9.4	8.0	7.7	0.3
318+00.00	318+50.00	20.3	17.2	3.2	14.0
318+50.00	319+00.00	29.0	24.6	1.8	22.9
319+00.00	319+50.00	36.6	31.1	0.7	30.3
319+50.00	320+00.00	40.1	34.1	0.0	34.1
320+00.00	320+50.00	37.6	32.0	0.7	31.2
320+50.00	321+00.00	28.8	24.5	2.3	22.2
321+00.00	321+50.00	22.1	18.8	3.8	15.0
321+50.00	322+00.00	28.2	24.0	2.5	21.5
322+00.00	322+50.00	49.4	41.9	0.3	41.7
322+50.00	323+00.00	77.0	65.5	0.0	65.5
TOTAL		1,595.0	1,355.8	2,714.1	-1,358.3

* ADJUSTED FOR SHRINKAGE (15%)

COMED ACCESS ROAD SUMMARY	
DESCRIPTION	QUANTITY
EARTH EXCAVATION	1,595
FURNISHED EXCAVATION	1,360

FILE NAME = Q:\DOT_25368367_US_34.ctb CN Ph2\Drawings\Advance Contr\Roadway\General\DL160T83-Sht-Sched_2.dgn



USER NAME = URS	DESIGNED - MB	REVISED -
	DRAWN - KJB	REVISED -
PLOT SCALE = / in.	CHECKED - SPF	REVISED -
PLOT DATE = 5/13/2013	DATE - 5/13/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	2012-0371	DUPAGE	45	10
CONTRACT NO. 60T83				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				