

100% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				A	B
			URBAN		
			0001 URBAN	0008 URBAN	
542A0226	PIPE CULVERTS, CLASS A, TYPE 1 21"	FOOT	20	20	
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	2	2	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	54		54
60616150	PAVED DITCH, TYPE A-60	FOOT	274	274	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	8	8	
67100100	MOBILIZATION	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
Z0013300	CONCRETE REMOVAL (SPECIAL)	SO YD	16	16	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	66		66
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SO FT	855		855
X0321963	MICRO-PILES	EACH	44		44
X0323433	MICROPILE PROOF LOAD TEST	EACH	1		1

* SPECIALTY ITEM

LEGEND

- A ROADWAY - 100% STATE
- B CONCRETE ARCH SN 022-3046 - 100% STATE

FILE NAME: I:\PROJECTS\2012\2012-0371\2012-0371.dwg



DESIGNED	MB	REVISED	
DRAWN	KJG	REVISED	
CHECKED	SPF	REVISED	
DATE	5/13/2013	REVISED	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	2012-0371	DUPAGE	45	6
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60TB3	