

PROPOSED DRAINAGE STRUCTURE SCHEDULE (CITY OF CHICAGO)

STRUCTURE	LOCATION	OFFSET	(EDGE OF PAVEMENT, EDGE OF SHOULDER, OR CENTER OF STRUCTURE)	RIM (ELEV)	N. INVERT (ELEV)	W. INVERT (ELEV)	E. INVERT (ELEV)	S. INVERT (ELEV)	NE. INVERT (ELEV)	NW. INVERT (ELEV)	SE. INVERT (ELEV)	SW. INVERT (ELEV)	TRENCH DRAIN	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	MANHOLES TYPE B, 4' DIA., TYPE 1 FRAME, CLOSED LID (CITY OF CHICAGO)	CATCH BASINS, TYPE A, 4' - DIAMETER, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	CATCH BASINS, TYPE A, 4' - DIAMETER, TYPE 1 FRAME, CLOSED LID (CITY OF CHICAGO)	MANHOLES TYPE A, 4' DIA., TYPE 1 FRAME, CLOSED LID (CITY OF CHICAGO)	PRECAST TUMBLING BASIN		
HARRISON STREET													EACH	EACH	EACH	EACH	EACH	EACH	EACH		
S-01	7805+19.81	29.02' LT	EOP	593.15			587.88									1					
S-02A	7807+00.09	25.20' RT	EOP	593.63	590.28									1							
S-02B	7807+00.02	19.34' RT	COS	593.72	590.22			590.26								1					
S-03	7807+09.45	32.00' LT	EOP	593.50			588.23									1					
S-51	7810+95.55	34.17' RT	-	597.37					594.85				1								
S-53	7810+92.00	16.00' RT	COS	597.60				581.29	581.29			594.71					1				
S-54	7811+25.00	8.73' LT	COS	596.81					581.16 (EX)			581.16			1						
S-55	7807+30.00	2.41' LT	COS	594.23		581.58	579.35												1		
HALSTED STREET																					
S-04	3831+70.00	36.50' RT	EOP	593.31		588.04	588.04									1					
S-04A	3831+69.63	73.44' RT	COS	593.42		588.24								1							
S-05A	3832+00.00	28.50' LT	EOP	593.18		587.91	587.91									1					
S-05B	3832+00.00	47.07' LT	COS	593.35			587.98							1							
S-06	3832+54.25	21.50' LT	EOP	593.63	588.50						587.25					1					
S-07	3838+16.50	21.63' LT	EOP	593.58				588.45	587.20							1					
S-08	3838+25.54	0.80' RT	COS	593.90	582.27													1			
60" COMBINED SEWER																					
S-56		CL	COS	594.83						579.17	579.17							1			
S-57		CL	COS	595.86						579.01	579.01 (EX)							1			
TOTAL													1	3	1	7	1	3	1		

FILE PATH = p:\388035\pmt\escomon\me\local\p\AECD\000\Documents\01_Americas\Transportation\60269938_Circle\Phase_1\000_CAD\006_Roadway_Sheets\60W26_Contract\0160W26-sht-Schedule-Drain-04



DI60W26-sht-Schedule-Drain-04
 USER NAME = chitua
 PLOT SCALE = 50.0000' / in.
 PLOT DATE = 9/12/2013

DESIGNED - AFC/JSL
 DRAWN - AFC
 CHECKED - EEY/JWC
 DATE - 9/15/13

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

DRAINAGE AND UTILITY SCHEDULES

SCALE: NTS SHEET 4 OF 6 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-008R	COOK	559	41
CONTRACT NO. 60W26			ILLINOIS FED. AID PROJECT	