

**TEMPORARY EROSION CONTROL SCHEDULE**

STAGES	MULCH, METHOD 2	MULCH, METHOD 4	TEMPORARY EROSION CONTROL SEEDING	PERIMETER EROSION BARRIER	INLET FILTERS
	ACRE	ACRE	POUND	FOOT	EACH
STAGE 1A	1.44	-	288	1506	80
STAGE 1B	1.61	-	322	1947	4
STAGE 2A	-	1.57	-	2504	12
STAGE 2B	-	1.58	-	2529	-
STAGE 3	-	1.24	-	1552	-
ROUNDED TOTAL	3.25	4.50	610	10,038	96

**TEMPORARY DRAINAGE SCHEDULE**

STAGE	STATION	TO	STATION	UPSTREAM INVERT	DOWNSTREAM INVERT	TRENCH BACK FILL	COMBINED SEWER (EXTRA STRENGTH VITRIFIED CLAY PIPE) 8 INCH (CDOOT)	COMBINED SEWER REMOVAL 8"
						CU YD	FOOT	FOOT
PRE-STAGE 1	3832+96	TO	3832+48	590.11	589.84	3.9	53	53
	3837+89	TO	3838+44	588.80	588.50	25.1	60	60
ROUNDED TOTAL						29.0	113	113

**PERMANENT EROSION CONTROL SCHEDULE**

PERMANENT CONDITION	NITROGEN FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MOWING	TOPSOIL FURNISH AND PLACE, 4"	SEEDING, CLASS 2A	EROSION CONTROL BLANKET	SODDING, SALT TOLERANT	SUPPLEMENTAL WATERING
	POUND	POUND	ACRE	SQ YD	ACRE	SQ YD	SQ YD	UNIT
PERMANENT CONDITION	272	272	1.25	9078	1.25	6030	2048	20.5
ROUNDED TOTAL	272	272	1.25	9078	1.25	6030	2048	20.5

FILE PATH = c:\388035\pmt\escomon\me\local\p\wec\000\Documents\01\_Americas\Transportation\60269938\_Circle\Phase\_1\000\_CAD\006\_Roadway\Sheets\60W26\_Contract\0160W26-sht-Eros-Schedule-01



DI60W26-sht-Eros-Schedule-01  
 USER NAME = chitua  
 PLOT SCALE = 50.0000' / in.  
 PLOT DATE = 9/14/2013

DESIGNED - AFC  
 DRAWN - AFC  
 CHECKED - DBM  
 DATE - 9/15/13

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**EROSION CONTROL SCHEDULES**

SCALE: SHEET 1 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-008R	COOK	559	122
CONTRACT NO. 60W26				
ILLINOIS FED. AID PROJECT				