


COM-ED = ELECTRIC COMPED - ELECTRIC
CITY OF CHICAGO = ELECTRIC
CITY OF CHICAGO WATER = WATER
IDOT LIGHTING= ELECTRIC
LEVEL 3 = FIBER OPTIC
MCI = FIBER OPTIC
MCI = FIBER OPTIC PEOPLE'S ENERGY = GAS

NOTE: ALL ELECTRONIC DEPTHS MARKED AS (ED) WERE OBTAINED UTILIZING A SONDE DEVICE. DEPTHS ON THE AT&T DUCT WERE RECORDED FROM AN AT&T CONTRACTOR. DEPTHS ON THE COMED DUCT WERE RECORDED BY A CARDNO CREW. CARDNO CAN NOT VERIFY THE ACCURACY OF THESE DEPTHS AND SHOULD BE USED AS APPROXIMATE AND AS INFORMATION ONLY.

UTILITIES SHOWN ON THESE PLANS AS DEPICTED IN THE LEGEND HAVE BEEN INVESTIGATED BY CARDNO IN ACCORDANCE WITH SUE INDUSTRY STANDARDS. ALL OTHER INFORMATION SHOWN HAS BEEN PROVIDED TO CARDNO BY OTHERS. CARDNO SUE FIELD INVESTIGATION WAS PERFORMED 3/4/13 THROUGH 7/30/13. CHANGES TO UTILITIES MAY HAVE BEEN MADE AND THEREFORE MAY RESULT IN VARIANCES FROM THIS PLAN. CONSIDERATION SHOULD BE GIVEN TO UPDATING THIS PLAN IF DEEMED ADVISABLE PRIOR TO FINAL DESIGN AND CONSTRUCTION.

PRELIMINARY DATA FOR DELIVERY 8/14/2013

ALL UTILITIES SHOWN QUALITY LEVEL "B" UNLESS NOTED OTHERWISE.







I-94/I-90/I-290 (Circle Interchange) Chicago, Illinois

F.A. SECTION				COUNTY	TOTAL SHEETS	SHEET NO.	
	N/A			Cook	559	156	
					Contract No. N/A		
FED. RO	DAD DIST.	NO.	ILLINOIS	Project No. P-91-259-12			

Utility Quality Level "A" : Visually Verified Test Hole Utility Quality Level "B" : Designating/non Visually Verified Test Hole

Utility Quality Level "C": Research with Survey Utility Quality Level "D": Records Research

DESIGNED	EG	REVISED	Ī
DRAWN	SRK	REVISED	
CHECKED	KFS	REVISED	
DATE	8/14/13	REVISED	
			ī

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**