

**SIGNING SCHEDULE**

LOCATION	SIGN NO.	LEGEND / DESCRIPTION	CODE	ACTION	LOCATION (STATION / OFFSET)				EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		NUMBER OF POSTS	REMOVE SIGN PANEL - TYPE 1	REMOVE SIGN PANEL - TYPE 2	REMOVE SIGN PANEL ASSEMBLY - TYPE A	REMOVE SIGN PANEL - TYPE 3	RELOCATE SIGN PANEL - TYPE 3	SIGN PANEL - TYPE 1	SIGN PANEL - TYPE 2	SIGN PANEL - TYPE 3	SIGN PANEL - TYPE 1 (SPECIAL)
					EXISTING	PROPOSED	WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)												
EB I-290	IKE-01-BM	HALSTED STREET 800 W	CUSTOM	REMOVE AND REPLACE SIGN	351+81.16	40.1' RT	351+81.45	45.4' RT	6.50	2.00	7.00	2.00	2		13.00					14.00		
	IKE-02-TS	SPEED LIMIT	R2-1	REMOVE AND REPLACE SIGN	351+35.03	40.3' RT	351+35.03	40.3' RT	3.00	4.00	3.00	4.00	1		12.00					12.00		
WB I-290	IKE-03-BM	HALSTED STREET 800 W	CUSTOM	REMOVE AND REPLACE SIGN	352+46.58	39.5' LT	352+50.83	36.2' LT	6.50	2.00	7.00	2.00	2		13.00					14.00		
SOUTHWEST RAMP	SW-01-BS	UNIVERSITY OF ILLINOIS AT CHICAGO NEXT 2 EXITS	CUSTOM	RELOCATED ON NEW POSTS	19+70.95	33.9' RT	19+75.92	33.0' RT	12.00	9.00	12.00	9.00	2			108.00	108.00					
EASTSOUTH RAMP	ES-03-TM	RAMP SPEED LIMIT 30	W13-3	REMOVE AND REPLACE SIGN	106+51.75	49.9' LT	106+37.41	46.8' LT	3.00	4.00	3.00	4.00			12.00					12.00		
	ES-04-BM	DOUBLE ARROWS	W12-1	REMOVE AND REPLACE SIGN	106+85.82	18.9' LT	106+80.99	16.0' LT	4.00	4.00	4.00	4.00	2		16.00					16.00		
TAYLOR EXIT RAMP	ES-01-GM	EXIT 52A - TAYLOR STREET/ROOSEVELT ROAD 1/4 MILE	CUSTOM	PROPOSED SIGN	-	-	7308+50.00	148.3' LT	-	-	16.00	11.00	2								176.00	
	-	EXIT 52A - TAYLOR STREET/ROOSEVELT ROAD 1/4 MILE	CUSTOM	RELOCATE SIGN	7809+00.00	33.0' LT	7308+50.00	12.7' LT	16.50	11.00	-	-	2					181.50				
NORTHWEST RAMP	NW-01-BM	ADDED LANE	W4-3R	REMOVE AND REPLACE SIGN	21+78.14	16.1' RT	21+79.19	15.9' RT	4.00	4.00	4.00	4.00	2		16.00					16.00		
ROUNDED SUBTOTAL													0	82	0	108	290	0	84	176	0	
TOTAL													85	82	1	108	290	59	84	176	46	

LOCATION	SIGN NO.	LEGEND / DESCRIPTION	CODE	ACTION	LOCATION (STATION / OFFSET)				EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		NUMBER OF POSTS	TELESCOPING STEEL SIGN SUPPORT	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	STEEL POST, SPECIAL	REMOVE GROUND MOUNTED SIGN SUPPORT	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	CONCRETE FOUNDATIONS	WOOD SIGN SUPPORT
					EXISTING	PROPOSED	WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)										
EB I-290	IKE-01-BM	HALSTED STREET 800 W	CUSTOM	REMOVE AND REPLACE SIGN	351+81.16	40.1' RT	351+81.45	45.4' RT	6.50	2.00	7.00	2.00	2	28.00						
	IKE-02-TS	SPEED LIMIT	R2-1	REMOVE AND REPLACE SIGN	351+35.03	40.3' RT	351+35.03	40.3' RT	3.00	4.00	3.00	4.00	1	16.00			1			
WB I-290	IKE-03-BM	HALSTED STREET 800 W	CUSTOM	REMOVE AND REPLACE SIGN	352+46.58	39.5' LT	352+50.83	36.2' LT	6.50	2.00	7.00	2.00	2	28.00						
SOUTHWEST RAMP	SW-01-BS	UNIVERSITY OF ILLINOIS AT CHICAGO NEXT 2 EXITS	CUSTOM	RELOCATED ON NEW POSTS	19+70.95	33.9' RT	19+75.92	33.0' RT	12.00	9.00	12.00	9.00	2				2	2	0.3	35.60
EASTSOUTH RAMP	ES-03-TM	RAMP SPEED LIMIT 30	W13-3	REMOVE AND REPLACE SIGN	106+51.75	49.9' LT	106+37.41	46.8' LT	3.00	4.00	3.00	4.00								
	ES-04-BM	DOUBLE ARROWS	W12-1	REMOVE AND REPLACE SIGN	106+85.82	18.9' LT	106+80.99	16.0' LT	4.00	4.00	4.00	4.00	2	32.00						
TAYLOR EXIT RAMP	ES-01-GM	EXIT 52A - TAYLOR STREET/ROOSEVELT ROAD 1/4 MILE	CUSTOM	PROPOSED SIGN	-	-	7308+50.00	148.3' LT	-	-	16.00	11.00	2		968.00				2.36	
	-	EXIT 52A - TAYLOR STREET/ROOSEVELT ROAD 1/4 MILE	CUSTOM	RELOCATE SIGN	7809+00.00	33.0' LT	7308+50.00	12.7' LT	16.50	11.00	-	-	2		924.00				2.36	
NORTHWEST RAMP	NW-01-BM	ADDED LANE	W4-3R	REMOVE AND REPLACE SIGN	21+78.14	16.1' RT	21+79.19	15.9' RT	4.00	4.00	4.00	4.00	2	32.00						
ROUNDED SUBTOTAL													136	1892	0	3	2	5.1	36	
TOTAL													151	1892	4	5	2	5.1	36	

FILE PATH = p:\388035-p\mt\escomon\me\local\p\AECD000\Documents\01\_Americas\Transportation\60269938\_Circle\Phase\_1\000\_CAD\006\_Roadway\Sheets\60W26-sht-Sign-Schedule-02A



D160W26-sht-Sign-Schedule-02A  
 USER NAME = chhua  
 PLOT SCALE = 50.0000' / in.  
 PLOT DATE = 9/13/2013

DESIGNED - OPS  
 DRAWN - OPS  
 CHECKED - DBM  
 DATE - 9/15/13

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SIGNING SCHEDULE**

SCALE: SHEET 2A OF 5 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-008R	COOK	559	184A
CONTRACT NO. 60W26				
ILLINOIS FED. AID PROJECT				