90 % FED 10 % STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY URBAN	CONSTRUCTION CODE: ROADWAY 0004 URBAN	BRIDGE 0011 016-1713	BRIDGE 0011 016-1716	RETAINING WALL 0040 016-1802	HIGHWAY LIGHTING 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN
X5610708	WATER MAIN REMOVAL, 8"	FOOT	25	25					
X5610712	WATER MAIN REMOVAL, 12"	FOOT	65	65					
X5610724	WATER MAIN REMOVAL, 24"	FOOT	32	32					
X5610736	WATER MAIN REMOVAL, 36"	FOOT	82	82					
X5860110	GRANULAR BACKFILL FOR STRUCTURES	CU YD	1006		381	625			
X6011705	PIPE DRAINS 6" (SPECIAL)	FOOT	18	18					
X6020083	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	3	3					
X6020270	MANHOLES TYPE B, 4' DIA., TYPE 1 FRAME, CLOSED LID (CITY OF CHICAGO)	EACH	1	1					
X6022505	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	7	7					
X6022712	CATCH BASINS, TYPE A, 4'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	2	2					
X6022900	CATCH BASINS TO BE RECONSTRUCTED (SPECIAL)	EACH	4	4					
X6023212	INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE, SPECIAL	EACH	2	2					
X6028000	MANHOLES TO BE RECONSTRUCTED (SPECIAL)	EACH	3	3					
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	21	19					2

* DENOTES SPECIALTY ITEM ** DENOTES NON-PARTICIPATING ITEM