90 % FED 10 % STATE

URBAN

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE: ROADWAY 0004 URBAN	BRIDGE 0011 016-1713	BRIDGE 0011 016-1716	RETAINING WALL 0040 016-1802	HIGHWAY LIGHTING 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN
*	X8950425	REMOVE EXISTING TRAFFIC SURVEILLANCE EQUIPMENT	L SUM	1					1	
	Z0004552	APPROACH SLAB REMOVAL	SQ YD	1203	1203					
	Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	154		154				
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
	Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	2			2			
	Z0018800	DRAINAGE SYSTEM	L SUM	1			1			
	Z0022800	FENCE REMOVAL	FOOT	392	392					
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	109	109					
*	Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	12					12	
	Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	678		182	326	170		
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
	Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	57	57					
	Z0062456	TEMPORARY PAVEMENT	SQ YD	3080	3080					
	X0327645	TEMPORARY SOIL RETENTION SYSTEM (SPECIAL)	SQ FT	303		303				

* DENOTES SPECIALTY ITEM * * DENOTES NON-PARTICIPATING ITEM

AECOM
303 EAST WACKER DRIVE, SUITE 1400
CHICAGO, IL 60601-5276
PHONE: (312) 373-7700 FAX: (312) 373-6800

0160W26-sht-500.dgn	DESIGNED - JWM	REVISED -
USER NAME = chue	DRAWN - JWM	REVISED -
PLOT SCALE = 1.0000 ' / in.	CHECKED - DBM	REVISED -
PLOT DATE = 9/16/2013	DATE - 9/15/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET 23 OF 26 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-008R	COOK	559	27A

CONTRACT NO. 60W26

ILLINOIS FED. AID PROJECT

FILE PATH = p:\\358839-pw-il.aecomonline.local\Pw6\0400\Documents\01 American Transportation\60260938 Circle\Phase II\003 C60\005 Roadway\Sheets\60W26 Contract\0160W26-sht-500.dgn