

CONSTRUCTION CODE

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				ROADWAY	BRIDGE	BRIDGE	RETAINING WALL	HIGHWAY LIGHTING	TRAFFIC SIGNALS	
				0004 URBAN	0011 016-1713	0011 016-1716	0040 016-1802	0021 URBAN	0021 URBAN	
* X0370172	LED LIGHT SOURCE FIXTURE FOR CANOPY LIGHTING (CTA)	EACH	36			36				
X0370173	PLUMBING - DOWNSPOUTS (CTA)	L SUM	1			1				
X0370174	STRUCTURAL STEEL (CTA)	L SUM	1			1				
* X0370175	CONCRETE FOUNDATION, 28" DIAMETER, 1 1/4" ANCHOR RODS, 15" BOLT CIRCLE (CDOT)	EACH	5					5		
* X0370073	REMOVE EXISTING MAST ARM AND LUMINAIRE (CDOT) AND REINSTALL	EACH	8					8		
*	GROUND ROD, 3/4" X 10'-0" LENGTH (CDOT)	EACH	11					11		
* X0370176	CONCRETE FOUNDATION, 24" DIAMETER, 1 1/4" ANCHOR RODS, 15" BOLT CIRCLE, 9 FEET (CDOT)	EACH	2						2	
* X0370177	CONCRETE FOUNDATION, 24" DIAMETER, 1 1/4" ANCHOR RODS, 15" BOLT CIRCLE, 7 FEET (CDOT)	EACH	4						4	
** X0370076	ROD AND CLEAN DUCT IN EXISTING CONDUIT SYSTEM (CDOT)	FOOT	94						94	
* X0370178	WIRELESS DETECTOR PACKAGE (CDOT)	EACH	2						2	
* X0370179	FLUSH MOUNTED WIRELESS SENSOR (CDOT)	EACH	15						15	
* X0370180	CAT 5 CABLE FOR WIRELESS DETECTOR (CDOT)	FOOT	811						811	
* X0370181	CONNECTORS FOR CAT 5 CABLE (CDOT)	EACH	5						5	

\* DENOTES SPECIALTY ITEM

\*\* DENOTES NON-PARTICIPATING ITEM



0160W26-ah-500.dgn	DESIGNED - JWM	REVISED -
USER NAME : phiva	DRAWN - JWM	REVISED -
PLOT SCALE : 1:8000' / in.	CHECKED - DBM	REVISED -
PLOT DATE : 9/16/2013	DATE - 9/15/13	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE:	SHEET 26	OF 26	SHEETS	STA.	TO STA.
--------	----------	-------	--------	------	---------

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-008R	COOK	559	270
CONTRACT NO. 60W26			ILLINOIS FED. AID PROJECT	

FILE PATH : c:\1\388039-01\int\online\local\p\16020438\Document\101\America\Transportation\60W26\938\_Circle\Phase 1\1600\_CAD\2013\_09\Drawings\Sheets\60W26-ah-500.dgn