

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE - 0021		
				GRAND AVENUE AT MT. PROSPECT ROAD / COUNTY LINE ROAD	GRAND AVENUE AT NORTHWEST AVENUE	GRAND AVENUE AT WOLF ROAD
				90% FEDERAL 7.5% STATE 2.5% DUPAGE COUNTY	90% FEDERAL 5% STATE 2.5% NORTHLAKE 2.5% PROLOGIS CO.	90% FEDERAL 10% STATE
81400300	DOUBLE HANDHOLE	EACH	2	-	-	2
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	1	1	-
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1214	-	-	1214
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1577	-	-	1577
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1462	-	-	1462
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1430	-	-	1430
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN NO. 14 1 PAIR	FOOT	2490	-	-	2490
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE NO. 6 2C	FOOT	268	-	-	268
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	867	-	-	867
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4	-	-	4
87700200	STEEL MAST ARM ASSEMBLY AND POLE 32 FT.	EACH	1	-	-	1
87700210	STEEL MAST ARM ASSEMBLY AND POLE 34 FT.	EACH	1	-	-	1
87700230	STEEL MAST ARM ASSEMBLY AND POLE 38 FT.	EACH	1	-	-	1
87700240	STEEL MAST ARM ASSEMBLY AND POLE 40 FT.	EACH	1	-	-	1

FILE NAME *	USER NAME * #USER*	DESIGNED - PKG	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES (SHEET 2 OF 5)				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
#FILE*		DRAWN - EA	REVISED -		SCALE: N.T.S.	SHEET NO.	OF	SHEETS	STA.	TO STA.	1376	2013-045TS	COOK	24	04
	PLOT SCALE * #SCALE*	CHECKED - PKG	REVISED -												
	PLOT DATE * #DATE*	DATE - 8/15/2013	REVISED -												
													CONTRACT NO. 60W98		
													FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT		