

25000210			
SEEDING, CLASS 2A			
STATION	STATION	LOCATION	ACRE
40th AVENUE			
135+44	137+23	RT	0.28
41st DRIVE CONNECTOR			
520+09	524+73	RT	0.39
520+36	524+69	LT	0.37
JOHN DEERE ROAD			
266+87	269+19	LT	0.10
COALTOWN ROAD			
10+00	10+19	LT	0.01
11+50	14+38	LT	0.06
14+47	18+28	LT	0.17
18+48	30+25	LT	1.59
27+62	32+00	RT	0.16
TOTAL			3.25

25000400		
NITROGEN FERTILIZER NUTRIENT		
AREA (ACRE)	APPLICATION RATE	POUND
JOBSITE		
SEEDING, CLASS 2A		
3.25	90 LB / ACRE	292.5
SODDING, SALT TOLERANT		
5.39	60 LB / ACRE	323.2
TOTAL		616

25000500		
PHOSPHORUS FERTILIZER NUTRIENT		
AREA (ACRE)	APPLICATION RATE	POUND
JOBSITE		
SEEDING, CLASS 2A		
3.25	90 LB / ACRE	292.5
SODDING, SALT TOLERANT		
5.39	60 LB / ACRE	323.2
TOTAL		616

25000600		
POTASSIUM FERTILIZER NUTRIENT		
AREA (ACRE)	APPLICATION RATE	POUND
JOBSITE		
SEEDING, CLASS 2A		
3.25	90 LB / ACRE	292.5
SODDING, SALT TOLERANT		
5.39	60 LB / ACRE	323.2
TOTAL		616

25100115			
MULCH, METHOD 2			
STATION	STATION	LOCATION	ACRE
38th STREET			
149+45	151+10	LT	0.05
149+78	150+98	RT	0.03
151+35	154+14	LT	0.15
156+52	157+29	LT	0.02
40th AVENUE			
131+35	132+04	LT	0.01
135+07	136+98	LT	0.10
41st DRIVE CONNECTOR			
534+78	535+24	LT	0.03
535+36	535+72	LT	0.01
535+84	537+78	LT	0.04
538+52	539+81	LT	0.04
540+16	540+66	LT	0.01
41st AVENUE DRIVE			
185+56	199+66	LT	0.55
185+56	186+97	RT	0.04
187+27	188+14	RT	0.03
188+44	193+65	RT	0.22
194+00	199+66	RT	0.25
200+35	200+80	LT	0.01
COALTOWN ROAD			
10+00	10+69	RT	0.09
10+30	13+90	LT	0.08
10+91	13+50	RT	0.11
13+96	14+36	LT	0.01
14+52	14+89	LT	0.01
14+95	18+32	LT	0.07
15+53	16+69	RT	0.13
16+97	22+32	RT	0.72
18+54	32+00	LT	0.28
22+48	24+17	RT	0.34
24+31	27+22	RT	0.12
TOTAL			3.75

25100125			
MULCH, METHOD 3			
STATION	STATION	LOCATION	ACRE
38th STREET			
151+38	154+86	RT	0.12
COALTOWN ROAD			
10+00	10+19	LT	0.01
27+61	32+00	RT	0.16
TOTAL			0.50

25100630			
EROSION CONTROL BLANKET			
STATION	STATION	LOCATION	SQ YD
40th AVENUE			
135+44	137+23	RT	1,359.1
41st DRIVE CONNECTOR			
520+09	524+73	RT	1,895.0
520+36	524+69	LT	1,814.7
JOHN DEERE ROAD			
1266+85	1269+32	LT	480.5
COALTOWN ROAD			
10+00	10+19	LT	50.1
18+28	22+75	LT	4,844.7
24+25	27+25	LT	1,188.5
27+62	30+25	RT	570.5
TOTAL			12,204

25100635			
HEAVY DUTY EROSION CONTROL BLANKET			
STATION	STATION	LOCATION	SQ YD
COALTOWN ROAD			
11+50	14+38	LT	274.8
14+47	18+28	LT	820.7
22+75	24+25	LT	817.8
27+25	30+25	LT	820.4
30+25	32+00	RT	207.3
TOTAL			2,941

25200110			
SODDING, SALT TOLERANT			
STATION	STATION	LOCATION	SQ YD
38th STREET			
149+45	150+98	RT	176.6
149+90	151+10	LT	228.5
151+35	154+14	LT	745.7
151+38	154+82	RT	595.0
155+27	158+53	RT	828.4
156+53	157+30	LT	74.2
40th AVENUE			
131+16	131+26	RT	6.6
131+35	132+05	LT	25.2
131+45	131+66	RT	20.2
131+88	133+59	RT	206.5
132+24	133+01	LT	129.9
133+13	133+63	LT	102.0
133+66	134+84	RT	268.1
133+71	134+94	LT	380.9
134+39	134+66	RT	34.8
134+73	135+05	RT	50.3
135+12	135+38	RT	61.0
135+39	135+99	RT	109.1
136+01	136+47	RT	54.9
136+47	136+89	RT	32.1
41st DRIVE CONNECTOR			
526+07	530+54	RT	2,595.2
526+04	534+42	LT	1,987.7
530+92	534+32	RT	2,040.9
534+71	535+23	LT	166.9
535+35	535+72	LT	25.3
535+84	537+78	LT	201.2
540+16	540+66	LT	43.9
41st AVENUE DRIVE			
185+56	199+66	LT	2,650.8
185+56	186+97	RT	212.8
187+27	188+14	RT	123.3
188+44	193+65	RT	1,065.5
194+00	199+66	RT	1,190.5
200+40	200+85	LT	49.3
COALTOWN ROAD			
10+00	10+69	RT	443.1
10+31	14+36	LT	432.5
10+91	13+50	RT	549.3
14+52	18+38	LT	388.3
15+53	16+69	RT	620.8
16+93	22+32	RT	3,488.0
18+45	32+00	LT	1,470.0
22+48	24+16	RT	1,613.2
24+33	27+22	RT	579.9
TOTAL			26,069

25200200		
SUPPLEMENTAL WATERING		
SODDING, SALT TOLERANT	APPLICATION RATE	UNIT
JOBSITE		
26,069.0	3 GAL / SQ YD	
78,207.0	1 UNIT / 1000 GAL	
78.2	15 APP	1,173.1
TOTAL		1,173

FILE NAME: c:\p\proj\0802393\08\cont-act-1\Design\Misc_Sheets\25200110-25200200-25200600-25200115-25200630-25200110.dgn



USER NAME = ntumbv	DESIGNED -	REVISED - ADDENDUM 1 8/15/2013
PLOT SCALE = 2.0000' / IN.	DRAWN -	REVISED -
PLOT DATE = 8/14/2013	CHECKED -	REVISED -
	DATE - 8/14/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.
--------	-----------	----	--------	------	----	------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	37
CONTRACT NO. 64B84			ILLINOIS FED. AID PROJECT	