

28000250						
TEMPORARY EROSION CONTROL SEEDING						
STATION	STATION	LOCATION	AREA (ACRE)	APPLICATION RATE	APPLICATIONS	POUND
38th STREET						
149+45	151+10	LT	0.05	100 LB / ACRE	4	15.6
149+78	150+98	RT	0.03	100 LB / ACRE	4	13.9
151+35	154+14	LT	0.15	100 LB / ACRE	4	61.6
151+38	154+39	RT	0.06	100 LB / ACRE	4	18.3
153+00	154+22	RT	0.02	100 LB / ACRE	4	6.9
154+22	154+82	RT	0.06	100 LB / ACRE	4	24.0
155+06	156+23	LT	0.04	100 LB / ACRE	4	16.6
155+49	158+53	RT	0.08	100 LB / ACRE	4	32.2
155+52	158+49	RT	0.05	100 LB / ACRE	4	21.0
156+52	157+29	LT	0.02	100 LB / ACRE	4	6.1
40th AVENUE						
131+16	131+26	RT	0.00	100 LB / ACRE	4	0.5
131+35	132+05	LT	0.00	100 LB / ACRE	4	0.4
131+45	131+65	RT	0.00	100 LB / ACRE	4	1.7
131+87	133+56	RT	0.02	100 LB / ACRE	4	6.2
131+89	133+52	RT	0.03	100 LB / ACRE	4	10.9
132+24	133+01	LT	0.03	100 LB / ACRE	4	10.7
133+13	133+60	LT	0.01	100 LB / ACRE	4	5.7
133+14	133+63	LT	0.01	100 LB / ACRE	4	2.7
133+66	134+84	RT	0.04	100 LB / ACRE	4	16.2
133+66	134+84	RT	0.01	100 LB / ACRE	4	5.9
133+71	134+94	LT	0.05	100 LB / ACRE	4	20.6
133+73	134+93	LT	0.03	100 LB / ACRE	4	10.9
134+39	134+66	RT	0.01	100 LB / ACRE	4	2.9
134+72	135+05	RT	0.01	100 LB / ACRE	4	4.2
135+07	136+98	LT	0.14	100 LB / ACRE	4	54.4
135+12	135+38	RT	0.01	100 LB / ACRE	4	5.0
135+20	137+50	RT	0.52	100 LB / ACRE	4	209.3
135+43	135+99	RT	0.02	100 LB / ACRE	4	9.0
136+01	136+48	RT	0.01	100 LB / ACRE	4	4.5
136+47	136+89	RT	0.01	100 LB / ACRE	4	2.6
41st DRIVE CONNECTOR						
520+09	524+74	RT	0.39	100 LB / ACRE	4	156.0
520+36	524+68	LT	0.38	100 LB / ACRE	4	152.5
526+04	533+56	LT	0.41	100 LB / ACRE	4	164.0
526+07	530+34	RT	0.44	100 LB / ACRE	4	176.0
531+17	534+33	RT	0.18	100 LB / ACRE	4	73.4
532+16	534+42	LT	0.08	100 LB / ACRE	4	32.0
534+78	535+24	LT	0.03	100 LB / ACRE	4	10.3
535+36	535+72	LT	0.01	100 LB / ACRE	4	2.1
535+84	537+78	LT	0.04	100 LB / ACRE	4	16.6
538+52	539+81	LT	0.04	100 LB / ACRE	4	15.3
540+16	540+66	LT	0.01	100 LB / ACRE	4	3.6
JOHN DEERE ROAD						
1266+85	1269+31	LT	0.11	100 LB / ACRE	4	42.1
41st AVENUE DRIVE						
185+56	199+66	LT	0.43	100 LB / ACRE	4	170.7
185+56	186+97	RT	0.04	100 LB / ACRE	4	16.8
187+27	188+14	RT	0.03	100 LB / ACRE	4	10.2
188+44	193+65	RT	0.22	100 LB / ACRE	4	88.1
194+00	199+66	RT	0.25	100 LB / ACRE	4	98.4
COAL TOWN ROAD						
10+00	10+19	LT	0.01	100 LB / ACRE	4	4.1
10+00	10+69	RT	0.09	100 LB / ACRE	4	36.6
10+30	13+90	LT	0.08	100 LB / ACRE	4	33.7
10+91	13+50	RT	0.11	100 LB / ACRE	4	45.4
11+50	13+50	LT	0.03	100 LB / ACRE	4	10.5
13+50	14+38	LT	0.03	100 LB / ACRE	4	12.2
13+96	14+36	LT	0.01	100 LB / ACRE	4	2.5
14+47	18+28	LT	0.17	100 LB / ACRE	4	67.8
14+52	14+89	LT	0.01	100 LB / ACRE	4	2.2
14+95	18+32	LT	0.07	100 LB / ACRE	4	28.1
15+53	16+69	RT	0.13	100 LB / ACRE	4	51.3
SUBTOTAL						2,123.2

28000250 (CON'T)						
TEMPORARY EROSION CONTROL SEEDING						
STATION	STATION	LOCATION	AREA (ACRE)	APPLICATION RATE	APPLICATIONS	POUND
16+97	22+32	RT	0.72	100 LB / ACRE	4	288.3
18+08	18+18	LT	0.00	100 LB / ACRE	4	0.4
18+45	32+00	LT	1.61	100 LB / ACRE	4	644.1
18+54	30+00	LT	0.28	100 LB / ACRE	4	111.7
22+48	24+17	RT	0.34	100 LB / ACRE	4	134.6
24+31	26+50	RT	0.12	100 LB / ACRE	4	47.9
27+61	32+00	RT	0.16	100 LB / ACRE	4	64.4
SUBTOTAL						1,291.3
TOTAL						3,415

28000305		
TEMPORARY DITCH CHECKS		
STATION	OFFSET	FOOT
38th STREET		
149+64	20.0 RT	14.0
157+15	33.0 RT	14.0
157+95	33.7 RT	14.0
40th AVENUE		
133+31	25.3 RT	14.0
133+33	27.9 LT	14.0
134+05	33.8 LT	14.0
135+56	162.5 RT	14.0
135+79	177.8 RT	14.0
135+82	48.1 LT	14.0
41st DRIVE CONNECTOR		
521+71	63.0 RT	16.0
522+02	37.2 LT	16.0
523+13	39.8 RT	16.0
523+46	27.5 LT	16.0
524+42	69.5 LT	16.0
526+53	123.6 RT	16.0
531+45	66.6 RT	16.0
531+99	56.9 RT	16.0
532+61	33.7 LT	16.0
532+87	52.3 RT	16.0
COAL TOWN RD		
30+49	24.2 LT	16.0
TOTAL		302

28000400				
PERIMETER EROSION BARRIER				
STATION	OFFSET	STATION	OFFSET	FOOT
38th STREET				
149+45	15.0 LT	149+65	15.0 LT	51.3
155+06	217.7 LT	156+23	50.8 LT	260.0
156+53	51.0 LT	157+00	43.4 LT	91.8
41st DRIVE CONNECTOR				
526+27	266.0 RT	135+00	73.6 LT	774.4
526+44	108.0 LT	532+18	35.2 LT	576.5
534+27	44.0 LT	534+42	160.0 LT	128.6
534+86	46.8 LT	535+23	33.0 LT	213.8
535+35	33.2 LT	535+72	33.0 LT	39.5
40th AVENUE				
133+65	40.0 LT	134+70	68.0 LT	122.7
41st AVENUE DRIVE				
185+56	30.7 LT	189+00	29.6 LT	372.7
185+56	33.3 RT	186+97	29.6 RT	172.5
187+27	29.6 RT	188+14	29.6 RT	87.8
188+44	29.6 RT	189+00	31.0 RT	56.4
194+00	35.9 RT	195+50	35.9 RT	136.3
COAL TOWN ROAD				
10+00	15.4 RT	10+69	114.8 RT	195.1
10+91	114.7 RT	524+43	107.5 RT	825.0
15+42	93.4 RT	16+73	60.0 RT	162.9
16+97	60.0 RT	22+32	259.3 RT	656.3
23+29	116.9 RT	24+17	88.6 RT	132.9
24+62	67.8 RT	27+12	53.9 RT	351.8
27+61	53.3 RT	32+00	15.0 RT	480.4
30+00	21.0 LT	32+00	15.0 LT	161.8
TOTAL				6,051

28000500		
INLET AND PIPE PROTECTION		
STATION	OFFSET	EACH
38th STREET		
149+71	21.6 RT	1
149+87	15.6 RT	1
40th AVENUE		
132+96	25.4 LT	1
133+50	27.9 RT	1
133+52	30.0 LT	1
133+81	32.6 RT	1
134+60	67.0 RT	1
134+68	35.9 RT	1
134+85	39.0 LT	1
135+01	103.1 RT	1
135+33	137.4 RT	1
135+68	169.5 RT	1
136+24	198.5 RT	1
136+74	222.2 RT	1
136+83	68.1 RT	1
41st DRIVE CONNECTOR		
524+54	54.6 RT	1
526+29	68.2 LT	1
527+50	27.6 LT	1
529+50	32.5 LT	1
532+84	33.3 LT	1
COAL TOWN RD		
10+47	14.7 RT	1
10+48	14.9 LT	1
11+10	20.8 RT	1
11+10	17.4 LT	1
13+65	24.0 LT	1
TOTAL		25

FILE NAME = c:\p\proj\0800305\08\convr.ac.t\Design\Misc_Sheets\0264884-ant-Sched04.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
6507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = ntumbv	DESIGNED -	REVISED - ADDENDUM 1 8/15/2013
PLOT SCALE = 2.0000' / IN.	DRAWN -	REVISED -
PLOT DATE = 8/14/2013	CHECKED -	REVISED -
	DATE - 8/14/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	38
CONTRACT NO. 64B84				
ILLINOIS FED. AID PROJECT				