

42000401 (CON'T)						
PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)						
STATION	STATION	LOCATION	LENGTH	WIDTH 1	WIDTH 2	SQ YD
5+65	5+68	FULL WIDTH	3.0	34.5	34.3	11.5
5+68	6+08	FULL WIDTH	40.0	34.3	28.6	139.8
6+08	6+28	FULL WIDTH	20.0	28.6	26.1	60.8
6+28	6+40	FULL WIDTH	12.0	26.1	24.9	34.0
6+40	6+50	FULL WIDTH	10.0	24.9	24.1	27.2
38TH STREET - NORTH						
162+08	162+48	FULL WIDTH	40.0	37.0		164.4
162+48	163+01	FULL WIDTH	53.0	37.0	42.0	232.6
163+01	163+35	FULL WIDTH	34.0	42.0	65.0	202.1
163+35	163+51	FULL WIDTH	16.0	65.0	109.9	155.5
163+51	163+62	FULL WIDTH	11.0	109.9	110.0	134.4
41ST STREET						
639+97	640+94	LT	97.0	32.9	33.1	355.7
640+94	641+28	LT	34.0	33.1	37.1	132.6
641+28	641+60	LT	32.0	37.1	48.6	152.4
641+60	641+74	LT	14.0	48.6	60.0	84.5
641+74	642+49	LT	75.0	60.0		500.0
642+49	642+61	LT	12.0	54.0		72.0
642+61	642+79	LT	18.0	54.0	40.7	94.7
642+79	643+01	LT	22.0	40.7	36.0	93.7
643+01	643+05	LT	4.0	36.0		16.0
SUBTOTAL						2,663.9
TOTAL						31,483

42001420						
BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)						
STATION	STATION	LOCATION	LENGTH	WIDTH 1	WIDTH 2	SQ YD
41ST DRIVE CONNECTOR						
523+15	523+41	FULL WIDTH	26.0	29.1	26.8	80.7
523+41	523+71	FULL WIDTH	30.0	26.8	26.0	89.3
523+71	524+15	FULL WIDTH	44.0	26.0		127.1
526+61	526+80	FULL WIDTH	19.0	26.0		27.4
526+80	527+00	FULL WIDTH	20.0	26.0	27.1	59.0
527+00	527+30	FULL WIDTH	30.0	27.1	32.8	99.8
527+30	527+61	FULL WIDTH	31.0	32.8	38.1	122.1
TOTAL						606

42100615						
PAVEMENT REINFORCEMENT						
STATION	STATION	LOCATION	LENGTH	WIDTH 1	WIDTH 2	SQ YD
41ST DRIVE CONNECTOR						
523+15	523+41	FULL WIDTH	26.0	29.1	26.8	80.7
523+41	523+71	FULL WIDTH	30.0	26.8	26.0	89.3
523+71	524+15	FULL WIDTH	44.0	26.0		127.1
526+61	526+80	FULL WIDTH	19.0	26.0		27.4
526+80	527+00	FULL WIDTH	20.0	26.0	27.1	59.0
527+00	527+30	FULL WIDTH	30.0	27.1	32.8	99.8
527+30	527+61	FULL WIDTH	31.0	32.8	38.1	122.1
TOTAL						606

42300300					
PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH					
STATION	LOCATION	LENGTH 1	LENGTH 2	WIDTH	SQ YD
38TH ST					
156+29	LT	12.0		6.0	8.0
		12.0	28.0	10.0	22.2
156+47	LT	12.0		6.0	8.0
		12.0	27.0	10.0	21.7
41ST AVE DRIVE					
187+12	RT	60.0	30.0	15.0	75.0
188+29	RT	60.0	30.0	15.0	75.0
193+82	RT	35.0		6.0	23.3
		35.0	65.0	15.0	83.3
41ST DRIVE CONNECTOR					
535+30	LT	1.4		12.0	1.9
		12.0	32.0	10.0	24.4
535+79	LT	1.4		12.0	1.9
		12.0	32.0	10.0	24.4
539+98	LT	45.6	34.8	6.0	26.8
		34.8	28.8	6.0	21.2
		28.8	26.9	6.5	20.1
534+46	RT	41.7	28.9	8.0	31.4
		28.9	24.0	9.4	27.6
		24.0		9.3	24.8
		24.0	34.8	14.3	46.7
		34.8	64.0	6.3	34.6
COAL TOWN RD					
10+25	LT	42.0	12.0	15.0	45.0
14+44	LT	32.0	12.0	10.0	24.4
10+79	RT	52.2	22.0	15.0	61.8
16+85	RT	24.0		23.8	63.5
	RT	24.4	54.8	15.0	66.0
24+12	RT	49.7	36.4	5.0	23.9
		30.0	36.4	9.3	34.3
		17.2		30.0	57.3
		38.4	25.8	27.2	97.0
		38.4	9.0	13.6	35.8
		9.0	0.8	7.0	3.8
		9.0	0.8	7.0	3.8
27+41	RT	32.1		35.0	124.8
		27.0	11.7	4.4	9.5
		11.7	1.0	11.5	8.1
		27.5	12.0	4.2	9.2
		12.0	1.0	11.6	8.4
35TH ST					
6+22	LT	27.0	54.0	15.0	67.5
TOTAL					1,347

FILE NAME: c:\p\proj\08031910\cont-act-1\Design\Misc-Sheets\026484-ent-Sched12.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
6507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = ntumbv	DESIGNED -	REVISED - ADDENDUM 1 8/15/2013
	DRAWN -	REVISED -
PLOT SCALE = 2.0000' / IN.	CHECKED -	REVISED -
PLOT DATE = 8/14/2013	DATE - 8/14/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES				
SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	46
CONTRACT NO. 64B84				
ILLINOIS FED. AID PROJECT				