

44300100						
AREA REFLECTIVE CRACK CONTROL TREATMENT						
STATION	STATION	LOCATION	LENGTH	WIDTH 1	WIDTH 2	SQ YD
COAL TOWN ROAD						
10+00.0	10+92.6	LT	92.6	24.95	25.1	257.5
10+92.6	13+32.6	LT	240.0	25.1	31.2	750.6
13+32.5	16+50.0	LT	317.5	31.2		1,100.8
TOTAL						2,109

48100300					
AGGREGATE SHOULDERS, TYPE A 4"					
STATION	STATION	LOCATION	LENGTH	WIDTH	SQ YD
41ST DRIVE CONNECTOR					
531+03	531+09	LT	6.0	3.9	2.6
531+09	534+21	LT	312.0	4.4	152.5
534+21	534+27	LT	6.0	2.0	1.3
534+69	534+79	LT	10.0	2.0	2.2
534+79	537+09	LT	230.0	4.4	112.4
537+09	537+36	LT	29.0	4.4	14.2
537+36	537+40	LT	4.0	3.9	1.7
531+15	534+20	RT	327.0	2.0	72.7
534+78	537+28	RT	252.0	2.0	56.0
TOTAL					416

48100500					
AGGREGATE SHOULDERS, TYPE A 6"					
STATION	STATION	LOCATION	LENGTH	WIDTH	SQ YD
40TH AVENUE					
131+35.4	131+61.8	LT	26.4	4.5	13.2
131+61.8	131+96.8	LT	35.0	4.0	15.6
132+31.5	132+92.7	LT	61.2	4.0	27.2
133+21.6	133+50.1	LT	28.5	4.0	12.7
133+79.7	134+85.5	LT	105.8	4.0	47.0
135+14.9	136+08.0	LT	93.1	4.0	41.4
131+96.1	133+47.4	RT	151.3	4.0	67.2
133+74.1	134+65.0	RT	90.9	4.0	40.4
135+38.1	136+80.7	RT	142.6	4.0	63.4
40TH AVE CONNECTOR					
821+21.4	821+79.8	LT	79.8	4.0	35.5
821+15.8	821+42.2	RT	45.5	4.0	20.2
39TH STREET					
140+55.0	141+60.0	LT	105.0	3.0	35.0
140+45.9	141+18.6	RT	76.4	3.0	25.5
141+18.6	141+60.0	RT	41.4	3.0	13.8
TOTAL					458

48102100						
AGGREGATE WEDGE SHOULDER, TYPE B						
STATION	STATION	LOCATION	LENGTH	WIDTH	CU YD	TON
40TH AVENUE						
120+54.0	120+70.2	LT	17.5	3.0	0.8	1.6
120+70.2	121+07.8	LT	37.6	3.0	1.7	3.5
121+76.6	123+44.2	LT	167.6	3.0	7.8	15.5
123+91.1	124+42.9	LT	51.8	3.0	2.4	4.8
120+84.5	121+06.0	RT	21.5	3.0	1.0	2.0
121+36.0	121+67.9	RT	31.9	3.0	1.5	3.0
121+96.0	122+24.0	RT	28	3.0	1.3	2.6
122+52.9	123+01.6	RT	48.7	3.0	2.3	4.5
123+35.6	123+56.8	RT	21.2	3.0	1.0	2.0
123+90.5	123+98.5	RT	8	3.0	0.4	0.7
TOTAL						41

48203021						
HOT-MIX ASPHALT SHOULDERS, 6"						
STATION	STATION	LOCATION	LENGTH	WIDTH 1	WIDTH 2	SQ YD
COAL TOWN ROAD						
30+00	31+10	LT	110.0	6.0	4.0	61.1
31+10	32+00	LT	90.0	4.0		40.0
30+00	30+53	RT	53.0	6.0	4.4	30.6
30+53	32+00	RT	147.0	4.4	4.0	71.9
TOTAL						204

48300400						
PORTLAND CEMENT CONCRETE SHOULDERS 9"						
STATION	STATION	LOCATION	LENGTH	WIDTH 1	WIDTH 2	SQ YD
41ST DR CONNECTOR						
530+02.37	531+10.00	LT	107.6	3.0		35.9
TOTAL						36

50105250			
PIPE CULVERT REMOVAL			
STATION	OFFSET	LOCATION	FOOT
COAL TOWN ROAD			
10+10	25	LT	27.0
13+64	0	RT	48.1
COAL TOWN ROAD			
3+20	34	RT	35.8
4+35	0	RT	40.0
38TH STREET			
153+52	0	RT	41.5
41ST AVENUE DRIVE			
187+98	18.7	RT	57.5
TOTAL			250

FILE NAME: c:\proj\080313\08\contract\1\design\misc\sheets\0264884-ant-sched15.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
6507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.776.4009 Fax 773.776.4014

USER NAME = espino	DESIGNED -	REVISED -
PLOT SCALE = 2.0000' / IN.	DRAWN -	REVISED -
PLOT DATE = 3/11/2013	CHECKED -	REVISED -
	DATE - 3/11/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1HB	ROCK ISLAND	507	49
ILLINOIS FED. AID PROJECT			CONTRACT NO. 64B84	