

DRAINAGE STRUCTURE SCHEDULE (CON'T.)					INVERT ELEVATION				54213657	54261415	54261418	54261424	54261427	54261430	54263415	60204505
STR NO	STA	OFFSET	RIM ELEV	WEIR ELEV	N	S	E	W	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	CONCRETE END SECTION, STANDARD 542001. 15", 1:4	CONCRETE END SECTION, STANDARD 542001. 18", 1:4	CONCRETE END SECTION, STANDARD 542001. 24", 1:4	CONCRETE END SECTION, STANDARD 542001. 27", 1:4	CONCRETE END SECTION, STANDARD 542001. 30", 1:4	CONCRETE END SECTION, STANDARD 542011, 15", 1:4	CATCH BASINS, TYPE A, 5'-DIA, TYPE 8 GRATE
									EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
59	195+08	26.08 L		573.82		566.88		566.88								
60	195+63	30.04 L	574.40		566.58	566.58										
61	196+80	34.00 R	572.24				566.36									
62	196+80	42.46 L		571.71	565.96		565.96	565.96								
63	197+70	40.2 R	571.17				567.18									
64	198+19	37.90 R	570.84				567.18									
65	198+51	34.44 L		570.33	565.65		565.65	566.63								
66	198+60	28.00 R		570.46			566.88	566.88								
67	199+21	33.22 R		570.81	566.55			566.55								
68	199+22	51.03 L		571.11		566.13	565.27	565.27								
69	642+63	83.34 R						564.25				1				
69A	640+10	72.08 R						562.90	1							
69B	640+10	35.08 L		570.71	566.51		566.41									
69C	640+90	37.47 L		570.94		566.88										
41ST DRIVE CONNECTOR																
70	521+05	66.56 L						578.10	1							
71	521+05	52.57 L	586.65				578.30	582.75								
72	521+05	15.54 R	593.06			587.90	587.80									
73	521+05	27.08 L		592.49			587.23	587.33								
74	521+05	19.13 R	593.12													
75	522+20	17.58 R	593.91													
76	522+20	14.00 R	593.86		589.00		589.10									
77	522+20	25.98 L	593.62					589.50								
78	524+50	41.42 L						566.91				1				
79	524+55	50.79 R					567.25					1				
80	526+28	64.20 L						566.28				1				
81	526+40	90.47 R						565.45				1				
82	527+50	22.58 L						569.40						1		
83	527+50	45.73 R						569.30						1		
84	527+78	30.58 R	589.04													
85	527+83	14.51 L	586.92					581.91								
86	527+83	27.00 R	586.66			581.39	581.49									
87	529+43	34.12 R	580.24													
88	529+43	30.53 R	580.19		575.31	574.25	574.35									
89	529+43	18.53 L	580.42					574.60								
90	529+50	27.29 L						565.00				1				
91	529+50	51.27 R					564.80					1				
92	530+00	36.73 R	577.76													
93	530+03	33.77 R	577.56		569.96	569.86										
94	531+13	20.00 L	573.65			566.62										
95	531+03	42.89 R	573.34		566.30		566.30									
96	531+86	23.71 R	571.69		565.84	565.84	565.84									
97	531+84	50.60 R			565.80							1				
98	532+35	20.99 R		570.28	565.91		565.91	565.91								
99	532+35	21.00 L		570.28		566.05										
100	532+83	33.19 L	568.29		565.21		566.12									1
101	533+03	21.08 R		569.79	566.02		566.02	566.02								
102	533+03	21.00 L		569.79		566.09		566.09								
103	533+96	21.00 R		569.51	566.44			566.44								
104	533+96	21.00 L		569.51		566.53	566.53									
105	534+22	31.09 L		569.21				566.59								
106	534+96	26.70 L		569.07			565.46									
107	535+10	21.53 L		569.15		565.39		565.39								
108	535+10	27.65 R		569.48	565.13		565.13									
109	536+00	33.00 R		568.50	564.68		564.68	564.68								
110	536+00	21.00 L		568.74		565.00										
111	536+90	33.00 R		567.61			564.23	564.23								
COAL TOWN ROAD																
112	11+10	15.44 L		591.11		587.25	587.15									
113	11+10	19.12 R		591.04	587.42											
114	11+90	28.63 R		591.58	587.92											
115	11+90	17.44 L		591.80		587.67	586.65	586.75								
SUBTOTAL									2	0	0	8	0	2	0	1

NOTES:

1. STA AND OFFSET FOR INLETS ARE AT THE CENTER POINT ON THE FACE OF INLET.
2. STA, OFFSET AND ELEVATION FOR MANHOLES ARE AT THE CENTER OF THE STRUCTURE.
3. STA, OFFSET AND ELEVATION FOR FLARED END SECTIONS ARE AT THE CONNECTION TO THE STORM SEWER.

FILE NAME = N:\PROJ\0808393\08\CONTRACT\1\Design\Misc_Sheets\0244884-ent-Sched18.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = odow	DESIGNED -	REVISD - ADDENDUM 1 8/15/2013
	DRAWN -	REVISD -
PLOT SCALE = 2.0000' / 1"	CHECKED -	REVISD -
PLOT DATE = 8/14/2013	DATE - 8/14/2013	REVISD -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)H	ROCK ISLAND	507	52
CONTRACT NO. 64B84				
ILLINOIS FED. AID PROJECT				