

STORM SEWER SCHEDULE				550A0050	550A0070	550A0120	550A0340	550A0360	550A0380	550A0410	550A0420	Z0056608	Z0056610	Z0056612	Z0056614	Z0056616	60107600	20800150
PIPE NO	FROM STR STA	TO STR STA	PIPE SLOPE	STORM SEWERS, CLASS A, TYPE 1 12"	STORM SEWERS, CLASS A, TYPE 1 15"	STORM SEWERS, CLASS A, TYPE 1 24"	STORM SEWERS, CLASS A, TYPE 2 12"	STORM SEWERS, CLASS A, TYPE 2 15"	STORM SEWERS, CLASS A, TYPE 2 18"	STORM SEWERS, CLASS A, TYPE 2 24"	STORM SEWERS, CLASS A, TYPE 2 27"	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	STORM SEWER (WATER MAIN REQUIREMENTS) 21 INCH	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	PIPE UNDERDRAINS 4"	TRENCH BACKFILL
				FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
60	196+80 RT	196+80 LT	0.55%				73											22.2
61	196+80 LT	198+51 LT	0.57%							54								
62	196+80 RT	197+70 RT															130	
63	196+80 LT	198+60 LT															68	
64	197+70 RT	198+51 LT	0.57%				97											9.8
65	197+70 RT	198+19 RT															74	
66	198+19 RT	198+60 RT	0.57%				53											4.0
67	198+19 RT	198+60 RT															55	
68	198+60 RT	198+60 LT															70	
69	198+51 LT	199+22 LT	0.50%							76								
70	198+60 RT	199+21 RT	0.49%				68											
71	198+51 LT	199+22 LT															87	
72	198+60 RT	199+21 RT															74	
73	199+21 RT	199+22 LT	0.50%				84											19.9
74	199+22 LT	642+63 RT	0.71%													144		53.2
74A	640+10 LT	640+10 RT	3.25%				108											
74B	640+90 LT	640+10 LT	0.50%				74											
41ST DRIVE CONNECTOR																		
75	521+05 LT	521+05 LT	1.67%				12											
76	521+05 LT	521+05 LT	22.40%				20											
77	521+05 RT	521+05 LT	1.15%				41											9.9
78	521+05 RT	521+05 LT															44	
79	522+20 RT	521+05 RT	0.98%				112											21.7
80	522+20 LT	522+20 RT	1.11%				36											4.2
81	527+83 LT	527+83 RT	1.11%				38											7.7
82	527+83 RT	529+43 RT	3.65%									166						33.3
83	529+43 LT	529+43 RT	0.56%				45											12.6
84	529+43 RT	530+03 RT	7.15%				60											22.7
85	531+13 LT	531+03 RT	0.53%				60											24.4
86	531+03 RT	531+86 RT	0.53%				87											30.0
87	531+10 RT	533+03 RT															196	
88	531+13 LT	533+03 LT															175	
89	531+86 RT	531+84 RT	0.18%						22									
90	532+35 RT	531+86 RT	0.15%						46									7.4
91	532+35 LT	532+35 RT	0.33%				42											7.2
92	533+03 RT	532+35 RT	0.17%			65												2.8
93	533+03 RT	535+10 RT															202	
94	532+83 LT	533+03 LT	0.19%			16												
95	533+03 LT	533+03 RT	0.17%			42												1.3
96	533+03 LT	533+96 LT															80	
97	533+96 RT	533+03 RT	0.46%										91					5.8
98	533+96 LT	533+96 RT	0.21%									42						1.6
99	534+22 LT	533+96 LT	0.32%	19														0.3
100	534+96 LT	535+10 LT	1.00%				7											0.8
101	535+10 LT	535+10 RT	0.53%									49						7.2
102	535+10 LT	537+30 RT															219	
103	535+10 RT	536+00 RT	0.54%				83											12.4
104	535+10 RT	536+90 RT															169	
105	536+00 LT	536+00 RT	0.59%									54						6.3
106	536+00 RT	536+90 RT	0.54%					83										7.0
107	536+90 RT	154+44 LT	0.32%					37										2.2
COALTOWN ROAD																		
108	11+10 RT	11+10 LT	0.49%				35											4.0
109	11+10 LT	11+90 LT	0.55%									73						14.1
110	11+90 RT	11+90 LT	0.54%				46											6.0
111	11+10 LT	13+35 LT															218	
112	11+10 RT	13+35 RT															221	
113	11+90 LT	13+35 LT	0.51%										138					47.0
114	13+35 LT	13+35 RT	0.56%					54										40.2
115	13+35 RT	13+45 RT	4.61%					28										
116	13+45 RT	13+55 RT	1.07%					28										
SUBTOTAL				19	0	123	1281	230	0	198	0	384	229	0	0	144	2082	448.9

FILE NAME: N:\PROJ\080393\08\CONTRACT\1\Design\Misc\_Sheets\026484-ent-Sched2.dgn



**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60656  
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = odow	DESIGNED -	REVISED - ADDENDUM 1 8/15/2013
PLOT SCALE = 2.0000' / 1"	DRAWN -	REVISED -
PLOT DATE = 8/14/2013	CHECKED -	REVISED -
	DATE - 8/14/2013	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1JR & 142-1HB)	ROCK ISLAND	507	58
CONTRACT NO. 64B84				
ILLINOIS FED. AID PROJECT				