

55100500						
STORM SEWER REMOVAL, 12"						
STATION	OFFSET	LOCATION	STATION	OFFSET	LOCATION	FOOT
38TH STREET SOUTH						
594+43	203.0	LT	594+22	35.5	LT	279.2
594+25	59.5	RT	594+54	76.0	RT	33.4
40TH AVENUE						
128+00	23.0	LT	127+94	13.0	RT	36.4
124+83	51.9	LT	125+19	75.0	LT	43.0
35TH STREET						
5+67	28.5	LT	5+67	17.9	RT	54.5
5+67	28.5	LT	18+85	60.6	RT	135.0
38TH STREET NORTH						
602+79	32.0	RT	602+79	53.0	LT	85.0
604+52	27.8	LT	604+51	37.8	LT	10.0
604+52	27.8	LT	604+51	42.4	RT	70.2
606+02	54.0	LT	605+97	60.6	LT	8.3
COAL TOWN ROAD						
1+73	14.0	LT	1+75	37.0	RT	51.0
COAL TOWN ROAD						
10+47	17.5	LT	10+47	17.1	RT	34.6
13+33	17.4	RT	13+34	17.1	LT	34.5
13+33	17.4	RT	13+35	24.7	RT	7.5
13+33	17.4	RT	13+61	18.8	RT	28.1
15+98	16.6	LT	15+98	33.3	RT	49.9
15+98	33.3	RT	15+98	70.1	RT	36.8
15+98	33.3	RT	16+50	36.1	RT	51.9
17+31	16.7	LT	17+32	42.2	RT	58.9
TOTAL						1,109

ADJUSTMENT SCHEDULE				60255500	60265700	60266100	60266600	X6026050	X6026051	Z0001110
LOCATION	EX RIM	PR RIM	MANHOLES TO BE ADJUSTED	VALVE VAULTS TO BE ADJUSTED	VALVE VAULTS TO BE RECONSTRUCTED	VALVE BOXES TO BE ADJUSTED	SANITARY MANHOLES TO BE ADJUSTED	SANITARY MANHOLES TO BE RECONSTRUCTED	GAS VALVE TO BE ADJUSTED	
			EACH	EACH	EACH	EACH	EACH	EACH		
38TH STREET SOUTH										
151+61	23.37 R	568.08	567.51							
154+84	33.34 L	567.30	568.45		1					
155+29	6.76 R	567.34	568.98						1	
155+58	32.81 R	567.82	568.51			1				
156+83	32.91 R	568.67	567.63							1
41ST DRIVE CONNECTOR										
534+01	12.62 L	569.08	570.12							1
534+10	23.98 L	568.80	570.31				1			
534+33	14.29 L	568.08	569.98				1			
534+43	18.57 L	569.14	569.86				1			
534+49	18.78 L	569.25	569.83				1			
534+59	5.37 R	569.10	570.06					1		
535+71	4.85 R	568.78	570.03					1		
35TH STREET										
5+21	19.44 R	597.45	596.00					1		
5+41	12.12 R	598.56	596.67				1			
5+77	14.61 R	600.36	598.73				1			
5+98	18.83 R	601.68	600.68	1						
COAL TOWN ROAD										
18+95	23.40 R	594.75	595.41					1		
20+77	13.65 L	597.70	589.56	1						
24+23	30.97 R	588.40	588.07					1		
27+62	24.72 R	591.50	591.96					1		
TOTAL				2	1	1	6	6	2	2

56400400			
FIRE HYDRANTS TO BE RELOCATED			
LOCATION	EACH		
STATION	L/R		
38TH STREET SOUTH			
154+16	39.64 R	1	
40TH AVENUE			
134+60	21.04 R	1	
124+16	26.40 L	1	
41ST AVENUE DRIVE			
192+47	20.08 R	1	
41ST DRIVE CONNECTOR			
534+27	41.36 L	1	
TOTAL			5

60500040			
REMOVING MANHOLES			
STATION	OFFSET	LOCATION	EACH
35TH STREET			
5+55	18.0	LT	1
5+69	18.0	RT	1
COAL TOWN ROAD			
10+46	17.5	LT	1
10+47	17.0	RT	1
13+33	17.0	RT	1
13+34	17.0	LT	1
18+86	61.0	RT	1
41ST DRIVE CONNECTOR			
528+48	23.0	RT	1
TOTAL			8

60500060			
REMOVING INLETS			
STATION	OFFSET	LOCATION	EACH
COAL TOWN ROAD			
10+46	17.0	RT	1
10+46	17.0	LT	1
13+34	17.0	RT	1
13+34	17.0	LT	1
20+31	78.5	RT	1
35TH STREET			
5+67	25.5	RT	2
5+67	18.0	LT	2
38TH STREET (NORTH)			
162+62	38.0	LT	1
162+78	14.0	LT	1
162+55	49.0	RT	1
162+80	36.0	RT	1
41ST AVENUE DRIVE			
538+76	26.0	RT	1
TOTAL			14

60600095		
CLASS SI CONCRETE (OUTLET)		
LOCATION	CU YD	
STATION	L/R	
38TH STREET SOUTH		
150+02	14.14 L	1.2
150+02	13.57 R	1.3
40TH AVENUE		
136+20	15.60 L	1.2
39TH AVENUE		
140+44	15.12 L	1.2
140+36	41.37 R	1.3
COAL TOWN ROAD		
30+00	20.11 L	1.2
30+00	20.29 R	1.3
TOTAL		8.7

56400500			
FIRE HYDRANTS TO BE REMOVED			
STATION	OFFSET	LOCATION	EACH
35TH STREET			
528+56	45.0	RT	1
TOTAL			1

60248700			
VALVE VAULTS, TYPE A, 4'-DIA, TYPE 1 FRAME, CLOSED LID			
LOCATION	EACH		
STATION	L/R		
38TH STREET SOUTH			
155+16	28.62 R	1	
TOTAL			1

FILE NAME: c:\p\proj\080319108\contract\1\design\misc\sheets\0264884-ant-sched26.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
6507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.776.4009 Fax 773.776.4014

USER NAME = espino	DESIGNED -	REVISED -
PLOT SCALE = 2.0000' / IN.	DRAWN -	REVISED -
PLOT DATE = 3/11/2013	CHECKED -	REVISED -
DATE = 3/11/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	60
CONTRACT NO. 64B84				
ILLINOIS FED. AID PROJECT				