

TRAFFIC SIGNAL QUANTITIES

PAY CODE	ITEM	UNIT	38TH ST & 41ST DR CONNECTOR	41ST DR CONNECTOR & 40TH AVE	COALTOWN RD & 41ST DR CONNECTOR	38TH ST & COALTOWN RD	INTERCONNECT	TOTALS
			QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	
87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1					1
87703010	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 56 FT.	EACH	1					1
87703030	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 60 FT.	EACH	2					2
87703040	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 62 FT.	EACH			1			1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16	4	4	8		32
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5	3.5	3.5	3.5		14
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT		20				20
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	15		37	35		87
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	63	21	21			105
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH		1	1	3		5
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	4	3	4	3		14
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH			3	1		4
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	8	3	4	3		18
88040230	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH		1				1
88040290	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4	1	1	1		7
88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH		2		2		4
88102845	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4		2	2		8
88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	12	6	8	6		32
88800100	PEDESTRIAN PUSH-BUTTON	EACH	8	2	6	6		22
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1					2
89502800	DISPOSITION OF SALVAGED TRAFFIC SIGNAL EQUIPMENT	L SUM						1
X8140105	HANDHOLE (SPECIAL)	EACH		2				2
X0326477	WIRELESS VEHICLE DETECTION AND WARNING SYSTEM COMPLETE	EACH	1	1	1	1		4
X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1	1	1	1		4
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1					2
XX007797	LUMINAIRES (SPECIAL)	EACH	4	3	4	3		14
B5900100	TRANSCEIVER	EACH	1	1	1	1		4

NOTE:
 1. THE ADDITIONAL QUANTITY INCLUDED IN THE TEMPORARY TRAFFIC SIGNAL INSTALLATION IS FOR 41ST ST AT 41ST AVENUE DRIVE.
 2. THIS PAY ITEM IS FOR THE INTERSECTION AT JOHN DEERE RD AND 38TH ST.

SEE NOTE 1

SEE NOTE 2

SEE NOTE 1

SQTY-2



2600 Warrenville Road, Suite 203, Downers Grove, IL 60515
 630.795.9119 voice, 630.839.2566 fax
 www.mps-il.com

MILLENNIA PROFESSIONAL SERVICES

DESIGNED - TVN	REVISED -
DRAWN - CJD	REVISED -
CHECKED - RPD	REVISED -
DATE - 3/11/2013	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

TRAFFIC SIGNAL PLAN SUMMARY OF QUANTITIES			
SCALE: 1=20	SHEET NO. OF	SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	285
FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 64884	