

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									SAFETY	
				80% FED 20% STATE						80% FED 20% CITY		100% CITY		
				ROADWAY	ROADWAY	BRIDGE	SAFETY	RETAINING WALL	RETAINING WALL	OTHER	SAFETY	FACILITIES		SAFETY
				0001	0004	0008	0021	0040	0040	0044	0021	0028		0021
				URBAN	URBAN	081-0176	URBAN	081-7002	081-7003	URBAN	URBAN	URBAN		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	596		596									
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	638		638									
20100500	TREE REMOVAL, ACRES	ACRE	1.40		1.40									
20101000	TEMPORARY FENCE	FOOT	345	72	273									
20200100	EARTH EXCAVATION	CU YD	47665	3103	44562									
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	33551	33551										
20400800	FURNISHED EXCAVATION	CU YD	16127	13909	2218									
20800150	TRENCH BACKFILL	CU YD	1431	679.15	751.85									
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	41040	10798	30242									
* 25000210	SEEDING, CLASS 2A	ACRE	3.25	0.77	2.48									
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	616	102	514									
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	616	102	514									
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	616	102	514									
* 25100115	MULCH, METHOD 2	ACRE	3.75	0.12	3.63									

14 * DENOTES SPECIALITY ITEM

FILE NAME: W:\PROJECTS\1001\CONTRACT_1\Design\Map_Sheet\0264884-sht-50001.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60655
Tel. 773.776.4009 Fax 773.776.4014

USER NAME: * espino	DESIGNED -	REVISED -
PLOT SCALE: 1/8" = 100.0000' / IN.	DRAWN -	REVISED -
PLOT DATE: 9/18/2013	CHECKED -	REVISED -
	DATE: 9/18/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES				
SCALE:	SHEET NO.	OF	SHEETS	STA. TO STA.

F.A.P. RTE.:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1)B	ROCK ISLAND	507	3
CONTRACT NO. 64884				
[ILLINOIS] FED. AID PROJECT				