

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									SAFETY	100% CITY		
				80% FED 20% STATE						80% FED 20% CITY		SAFETY			FACILITIES	
				ROADWAY	ROADWAY	BRIDGE	SAFETY	RETAINING WALL	RETAINING WALL	OTHER	SAFETY					SAFETY
				0001	0004	0008	0021	0040	0040	0044	0021					0028
URBAN	URBAN	081-0176	URBAN	081-7002	081-7003	URBAN	URBAN	URBAN								
* 81028750	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA.	FOOT	2163										2113		50	
* 81028760	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2 1/2" DIA.	FOOT	78										78			
* 81028770	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 3" DIA.	FOOT	603										523		80	
* 81028790	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 4" DIA.	FOOT	752										752			
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	3429										1219		2210	
* 81301200	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 12" X 10" X 6"	EACH	9										6		3	
* 81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	24										22		2	
* 81400740	DOUBLE HANDHOLE, COMPOSITE CONCRETE	EACH	5										5			
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	3187										3187			
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	326										326			
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	6		6											
* 85900100	TRANSCEIVER	EACH	4										4			
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	3213										3213			
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	3341										3341			
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3728										3728			

\* DENOTES SPECIALITY ITEM

FILE NAME: I:\PROJ\88031913\CONTRACT\1\Design\Visc\_Sheets\026-684-011-60015.dgn



**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60655  
Tel: 773.776.4009 Fax: 773.776.4014

USER NAME = espino	DESIGNED -	REVISED -
PLOT SCALE = 1/8" = 1'-0"	DRAWN -	REVISED -
PLOT DATE = 9/18/2013	CHECKED -	REVISED -
	DATE = 9/18/2013	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(142-1)R & 142-1HB	ROCK ISLAND	507	17
CONTRACT NO. 64884				
ILLINOIS FED. AID PROJECT				