

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				80% FED 20% STATE					80% FED 20% CITY		100% CITY		
				ROADWAY	ROADWAY	BRIDGE	SAFETY	RETAINING WALL	RETAINING WALL	OTHER	RETAINING WALL	SAFETY	
				0001	0004	0008	0021	0040	0040	0044	0040	0021	
				081-7002	081-7003	URBAN	081-P002	081-P003	URBAN				
60602500	CONCRETE GUTTER, TYPE A	FOOT	850								850		
* X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	12924								11954	970	
* X0324456	DRILLING AND SETTING SOLDIER PILES (IN ROCK)	CU FT	3797								3633	164	
* Z0007118	UNTREATED TIMBER LAGGING	SO FT	5958								5958		
Z0025505	PROPERTY MARKERS	EACH	20		20								
* Z0026402	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	372									372	
* Z0026404	FURNISHING SOLDIER PILES (W SECTION)	FOOT	3176								3176		
Z0026407	TEMPORARY SHEET PILING	SO FT	439			439							
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SO FT	30815					15837	14978				
Z0046306	PIPE UNDERDRAINS FOR STRUCTURES 6"	FOOT	850								850		
* Z0054400	ROCK FILL	CU YD	22819	22819									
Z003798	CONSTRUCTION LAYOUT	L.SUM	1		1								
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	1286	311	975								
Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	484	91	393								
Z0056612	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	116		116								
Z0056614	STORM SEWER (WATER MAIN REQUIREMENTS) 21 INCH	FOOT	109		109								
Z0056616	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	201		201								
Z0062456	TEMPORARY PAVEMENT	SO YD	1112	211	901								
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SO FT	22186					8093	12719		1374		
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2		2								
Z0074100	TERMINATION OF DEAD END ROADS	EACH	2				2						
⊙ Z0076600	TRAINEES	HOUR	2000		2000								
⊙ Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	2000		2000								

* DENOTES SPECIALITY ITEM
⊙ 0042

FILE NAME: \\p100\A0003390\00\comp-001\Urban\gh\mso_ghw\sa\0264854-311-9002.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel: 773.775.4009 Fax: 773.775.4014

USER NAME * gspino	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE * 1/8" = 1' IN.	CHECKED -	REVISED -
PLOT DATE * 9/18/2013	DATE * 9/18/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 595	SECTION 142-1R & 142-1HB	COUNTY ROCK ISLAND	TOTAL SHEETS 507	SHEET NO. 24
CONTRACT NO. 648B4				
ILLINOIS FED. AID PROJECT				