

**BEAM 11**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. of W. Abut.	426+35.79	13.90	643.92	643.92
☉ of W. Abut.	426+38.15	13.91	643.94	643.94
A	426+48.17	13.94	644.00	644.02
B	426+58.18	13.97	644.06	644.10
C	426+68.19	13.99	644.13	644.17
D	426+78.20	14.00	644.20	644.22
E	426+88.21	14.00	644.27	644.28
☉ Brg. Pier 1	426+93.72	14.00	644.31	644.31
F	427+03.73	13.98	644.39	644.40
G	427+13.75	13.96	644.47	644.50
H	427+23.76	13.93	644.55	644.60
I	427+33.77	13.89	644.63	644.68
J	427+43.78	13.84	644.70	644.74
K	427+53.79	13.79	644.77	644.79
☉ Brg. Pier 2	427+63.31	13.72	644.84	644.84
L	427+73.32	13.65	644.90	644.91
M	427+83.33	13.57	644.96	644.99
N	427+93.34	13.47	645.02	645.05
O	428+03.35	13.37	645.07	645.10
P	428+13.36	13.27	645.11	645.13
☉ of E. Abut	428+18.87	13.20	645.14	645.14
Bk. of E. Abut.	428+21.23	13.17	645.15	645.15

**BEAM 12**

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. of W. Abut.	426+43.44	21.60	643.81	643.81
☉ of W. Abut.	426+45.80	21.60	643.83	643.83
A	426+55.82	21.63	643.89	643.92
B	426+65.84	21.65	643.96	644.00
C	426+75.86	21.66	644.03	644.07
D	426+85.88	21.67	644.10	644.12
E	426+95.90	21.66	644.18	644.18
☉ Brg. Pier 1	427+01.41	21.65	644.22	644.22
F	427+11.43	21.63	644.30	644.31
G	427+21.45	21.60	644.38	644.41
H	427+31.47	21.57	644.46	644.51
I	427+41.48	21.52	644.53	644.58
J	427+51.50	21.47	644.60	644.64
K	427+61.52	21.40	644.67	644.69
☉ Brg. Pier 2	427+71.04	21.33	644.73	644.73
L	427+81.06	21.25	644.79	644.80
M	427+91.08	21.16	644.85	644.88
N	428+01.09	21.06	644.90	644.94
O	428+11.11	20.96	644.95	644.98
P	428+21.13	20.84	644.99	645.01
☉ of E. Abut	428+26.64	20.77	645.02	645.02
Bk. of E. Abut.	428+29.00	20.74	645.03	645.03



USER NAME = DESIGNED - JAD CHECKED - SJN PLOT SCALE = DRAWN - JAD PLOT DATE = CHECKED - SJN	REVISED - REVISED - REVISED - REVISED -
---	--

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**TOP OF SLAB ELEVATIONS**  
**STRUCTURE NO. 006-0184 (E.B.) & 006-0185 (W.B.)**  
 SHEET NO. 8 OF 43 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(06-2)BR-3,4	BUREAU	133	52
CONTRACT NO. 66998			ILLINOIS FED. AID PROJECT	