

90% FED.
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				ROADWAY	BRIDGE				
				0004	0011				
51200958	FURNISHING METAL SHELL PILES 14" X 0.250"	FOOT	2,669		2,669				
51202305	DRIVING PILES	FOOT	4,877		4,877				
51203000	TEST PILES PRECAST CONCRETE	EACH	4		4				
51203200	TEST PILE METAL SHELLS	EACH	8		8				
51500100	NAME PLATES	EACH	2		2				
52100520	ANCHOR BOLTS, 1"	EACH	96		96				
54200229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	591	591					
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	188		188				
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	6	6					
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	117	117					
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	789.8	789.8					
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1					
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	7	7					
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	4	4					

* SPECIALTY ITEMS

FILE NAME = D366998-shv-500.dgn	USER NAME = brian.heil	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE. 80	SECTION 106-2) BR-3,4	COUNTY BUREAU	TOTAL SHEETS 133	SHEET NO. 6		
	PLOT TIME = 11:46:43 AM	DRAWN -	REVISED -			SCALE:	SHEET 4 OF 8 SHEETS	STA.	TO STA.	CONTRACT NO. 66998		
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -			ILLINOIS FED. AID PROJECT						
	PLOT DATE = 7/31/2013	DATE -	REVISED -									