




STAGE I REMOVAL



STAGE I CONSTRUCTION




STAGE II REMOVAL




STAGE II CONSTRUCTION

Notes:
 All staging cross sections are looking East.
 Horizontal dimensions in staging cross sections are at right angles to $\text{\textcircled{C}}$ F.A.P. Rte. 311.
 For quantity of Temporary Concrete Barrier, see roadway plans.
 Hatched area indicates Removal of Existing Structures.
 A cantilevered sheet piling design does not appear feasible and additional members or other retention systems may be necessary. The Contractor shall submit a temporary soil retention system design including plan details and calculations for review and acceptance by the Engineer.



EAST TEMPORARY SOIL RETENTION SYSTEM

(Looking South) - Horizontal dimensions for Temporary Soil Retention System are given along $\text{\textcircled{C}}$ F.A.P. Rte. 311.



WEST TEMPORARY SOIL RETENTION SYSTEM

(Looking South) - Horizontal dimensions for Temporary Soil Retention System are given along $\text{\textcircled{C}}$ F.A.P. Rte. 311.


DESIGNED - RAY AHANCHI	EXAMINED - <i>James F. J. [Signature]</i>	DATE - OCTOBER 1, 2013
CHECKED - AL-BARRAE R. SHEBIB	ACTING ENGINEER OF BRIDGE DIVISION	
DRAWN - MICHAEL B. MOSSMAN	PASSED - <i>Carl [Signature]</i>	REVISED -
CHECKED - G.R.A. / A.R.S.	ACTING ENGINEER OF BRIDGES AND STRUCTURES	REVISED -

STAGE CONSTRUCTION DETAILS
STRUCTURE NO. 050 - 2651

SHEET NO. 2 OF 11 SHEETS

Added 10-29-13

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(4)BR-1	LASALLE	38	19
CONTRACT NO. 66B13				
ILLINOIS FED. AID PROJECT				




SECTION A-A
Horizontal dimensions are at
Rt. L's to @ F.A.P. Rte. 311


Note:
The geotextile soil reinforcement shall have a minimum allowable tensile strength (T min.) of 25 lb./in. as determined by the procedure described in the Special Provision. The computations supporting the determination of (T min.) shall be submitted to the Engineer for approval.

LEGEND


- Indicates limits of geotextile wall
- Indicates limits of select fill



PLAN




1. Place form brace system on completed reinforcement level; back from the finished fabric face a distance of $\frac{1}{3}$ to $\frac{1}{2}$ the geotextile reinforcement spacing.
2. Position fabric so that the required geotextile re-embedment length extends over the top of the form brace and the design reinforcement width is placed with no slack against the previous level.
3. Compact select fill material in lifts to final lift height, create ($\pm 3''$) depression in zone where re-embedment length will be located and place additional height of compacted select fill against form brace.




4. Fold geotextile re-embedment length back over form brace into zone where depression was made in select fill and place additional select fill ($\pm 3''$) to embed geotextile and bring to final lift height.
5. Pull form brace outward allowing geotextile face to slightly readjust to form tight round face level with plan reinforcement spacing.

**GEOTEXTILE WALL
CONSTRUCTION SEQUENCE**



PLAN



SECTION B-B

**GEOTEXTILE
FORM BRACE DETAIL**

This is a suggested detail, the Contractor is responsible for the design of the form brace system to be used.

Added 10-29-13

DESIGNED - RAY AHANCHI	EXAMINED - <i>James F. J...</i>	DATE - OCTOBER 1, 2013
CHECKED - AL-BARRAE R. SHEBIB	PASSED - <i>Michael B. Mossman</i>	REVISED -
DRAWN - MICHAEL B. MOSSMAN	ACTING ENGINEER OF BRIDGES AND STRUCTURES	REVISED -
CHECKED - G.R.A. / A.R.S.		


**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**GEOTEXTILE RETAINING WALL
STRUCTURE NO. 050 - 2651**

SHEET NO. 3 OF 11 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(4)BR-1	LASALLE	38	20
				CONTRACT NO. 66B13
ILLINOIS FED. AID PROJECT				

When "A" is 3'-6" or less, the temporary concrete barrier shall be anchored to the new slab according to Detail I or Detail II. No anchorage is required when "A" is greater than 3'-6".



SECTIONS THRU SLAB OR DECK BEAM

NOTES


Detail I - With Bar Splicer or Couplers:
Connect one (1) 1" x 7" x "W" steel \bar{L} to the top layer of couplers with 2-5/8" ϕ bolts screwed to coupler at approximate \bar{C} of each barrier panel.

Detail II - With Extended Reinforcement Bars:
Connect one (1) 1" x 7" x "W" steel \bar{L} to the concrete slab or concrete wearing surface with 2-5/8" ϕ Expansion Anchors or cast in place Inserts spaced between the top layer of reinforcement at approximate \bar{C} of each barrier panel.


Cost of anchorage is included with Temporary Concrete Barrier. The 1" x 7" x "W" plate shall not be removed until stage II construction forms and all reinforcement bars are in place and the concrete is ready to be placed.

*** Dimension shown is minimum required embedment into concrete. If hot-mix asphalt wearing surface is present, minimum embedment shall be in addition to wearing surface depth.


**** If existing deck beam is to remain in place after stage construction, embedment shall only be into wearing surface and not into existing deck beam concrete.



DETAIL I



DETAIL II



STEEL RETAINER 1" x 7" x "W"

* Required only with Detail II

** Wood blocks may be omitted when required to provide minimum stage traffic lane width. When the wood blocks are omitted, the concrete barrier shall be in direct contact with the steel retainer plate.



"W" = Top bars spacing + 4"

R-27


7-1-10

Added 10-29-13


DESIGNED - RAY AHANCHI	EXAMINED - <i>Joanna F. Duff</i>	DATE - OCTOBER 1, 2013	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION STRUCTURE NO. 050 - 2651	F.A.P. RTE. 311	SECTION (4)BR-1	COUNTY LASALLE	TOTAL SHEETS 38	SHEET NO. 21	
CHECKED - AL-BARRAE R. SHEBIT	PASSED - <i>Carl King</i>	REVISED -			CONTRACT NO. 66B13					
DRAWN - MICHAEL B. MOSSMAN	ACTING ENGINEER OF BRIDGES AND STRUCTURES	REVISED -			SHEET NO. 4 OF 11 SHEETS					
CHECKED - G.R.A. / A.R.S.					ILLINOIS FED. AID PROJECT					



MINIMUM BAR LAP
#4 Bar = 2'-7"



DRAIN DETAIL
(Downstream end)



DRAIN DETAIL
(Upstream end)

PLAN

Added 10-29-13


DESIGNED - RAY AHANCHI	EXAMINED	DATE - OCTOBER 1, 2013
CHECKED - AL-BARRAE R. SHEBIB	PASSED	REVISOR
DRAWN - MICHAEL B. MOSSMAN		REVISOR
CHECKED - C.R.A. / A.R.S.		REVISOR

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CULVERT DETAILS - TOP SLAB
STRUCTURE NO. 050 - 2651

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(4)BR-1	LASALLE	38	22

CONTRACT NO. 66B13
ILLINOIS FED. AID PROJECT



PLAN


Added 10-29-13

DESIGNED - RAY AHANCHI	EXAMINED - <i>Jayne F. [Signature]</i>	DATE - OCTOBER 1, 2013
CHECKED - AL-BARRAE R. SHEBIB	PASSED - <i>[Signature]</i>	REVISED -
DRAWN - MICHAEL B. MOSSMAN	ACTING ENGINEER OF BRIDGES AND STRUCTURES	REVISED -
CHECKED - G.R.A. / A.R.S.		


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CULVERT DETAILS - BOTTOM SLAB
STRUCTURE NO. 050 - 2651
SHEET NO. 6 OF 11 SHEETS

F.A.P. RTE. 311	SECTION (4)BR-1	COUNTY LASALLE	TOTAL SHEETS 38	SHEET NO. 23
CONTRACT NO. 66B13				
ILLINOIS FED. AID PROJECT				



LONGITUDINAL SECTION
(Looking East)



SECTION THRU BARREL
(Dimensions are at Rt. L's unless otherwise noted).

* Dimensions taken at Rt. L's to \odot F.A.P. Rte. 311.

DESIGNED - RAY AHANCHI
 CHECKED - AL-BARRAE R. SHEBIB
 DRAWN - MICHAEL B. MOSSMAN
 CHECKED - G.R.A. / A.R.S.

EXAMINED - *Joyce F. [Signature]*
 ACTING ENGINEER OF BRIDGE DIVISION
 PASSED - *[Signature]*
 ACTING ENGINEER OF BRIDGES AND STRUCTURES


DATE - OCTOBER 1, 2013
 REVISED
 REVISED

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

CULVERT DETAILS
 STRUCTURE NO. 050 - 2651
 SHEET NO. 7 OF 11 SHEETS

F.A.P. RTE. 311	SECTION (4)BR-1	COUNTY LASALLE	TOTAL SHEETS 38	SHEET NO. 24
			CONTRACT NO. 66813	
ILLINOIS FED. AID PROJECT				

Added 10-29-13






SECTION A-A

LONG WINGWALL


SHORT WINGWALL

SECTION B-B

END ELEVATION



WINGWALL PLAN A
(NE and SW wingwalls)




WINGWALL PLAN B
(NW and SE wingwalls)


Note:
A distance of half the length of the wingwall, but not less than six feet of the barrel, shall be poured monolithically with the wingwalls.

Added 10-29-13


DESIGNED - RAY AHANCHI	EXAMINED - <i>James F. J...</i>	DATE - OCTOBER 1, 2013	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		CULVERT DETAILS		F.A.P. RTE. 311	SECTION (4)BR-1	COUNTY LASALLE	TOTAL SHEETS 38	SHEET NO. 25
CHECKED - AL-BARRAE R. SHEBIB	PASSED - <i>Michael B. Mossman</i>	REVISED -			STRUCTURE NO. 050 - 2651						
DRAWN - MICHAEL B. MOSSMAN	ACTING ENGINEER OF BRIDGES AND STRUCTURES	REVISED -	SHEET NO. 8 OF 11 SHEETS		ILLINOIS FED. AID PROJECT						
CHECKED - G.R.A. / A.R.S.											




**GABION WINGWALL
ISOMETRIC VIEW**




BAR d(E)



BAR d(E)




BARS h4(E) & h5(E)




BARS h6(E) & h7(E)


LEGEND
 Indicates area of exposed gabion




GABION SIZE
 Dimensions are (Length x Width x Height).



BAR s(E)



BARS s1(E) & s2(E)




**GABION WINGWALL
END VIEW**

Note:
 Cost of Filter Fabric, excavation, and backfill behind gabions is included with Gabions.

BILL OF MATERIAL

Bar	No.	Size	Length	Shape
d(E)	326	#6	24'-1"	
a1(E)	326	#6	17'-0"	
a2(E)	168	#4	5'-6"	
d(E)	38	#4	4'-6"	
h(E)	120	#5	37'-9"	
h1(E)	120	#5	42'-5"	
h2(E)	16	#7	22'-9"	
h3(E)	6	#4	23'-0"	
h4(E)	44	#7	18'-6"	
h5(E)	30	#7	11'-4"	
h6(E)	38	#7	14'-2"	
h7(E)	26	#7	9'-2"	
s(E)	23	#4	5'-1"	
s1(E)	46	#4	5'-3"	
s2(E)	23	#4	5'-5"	
v(E)	432	#5	9'-9"	
v1(E)	16	#5	12'-6"	
Concrete Box Culverts			Cu. Yd.	203.6
Reinforcement Bars, Epoxy Coated			Pound	40,590

Added 10-29-13



STANDARD BAR SPLICER ASSEMBLY


Bar size to be spliced	Minimum Lap Lengths					
	Table 1	Table 2	Table 3	Table 4	Table 5	Table 6
3, 4	1'-5"	1'-11"	2'-1"	2'-4"	2'-7"	2'-11"
5	1'-9"	2'-5"	2'-7"	2'-11"	3'-3"	3'-8"
6	2'-1"	2'-11"	3'-1"	3'-6"	3'-10"	4'-5"
7	2'-9"	3'-10"	4'-2"	4'-8"	5'-2"	5'-10"
8	3'-8"	5'-1"	5'-5"	6'-2"	6'-9"	7'-8"
9	4'-7"	6'-5"	6'-10"	7'-9"	8'-7"	9'-8"

- Table 1: Black bar, 0.8 Class C
- Table 2: Black bar, Top bar lap, 0.8 Class C
- Table 3: Epoxy bar, 0.8 Class C
- Table 4: Epoxy bar, Top bar lap, 0.8 Class C
- Table 5: Epoxy bar, Class C
- Table 6: Epoxy bar, Top bar top, Class C

Threaded splicer bar length = min. lap length + 1/2" + thread length


* Epoxy not required on Bar Splicer Assembly components used in conjunction with black bars.

Location	Bar size	No. assemblies required	Table for minimum lap length
Top slab	#5	42	5
Walls	#5	36	5
Bottom slab	#5	42	5




INSTALLATION AND SETTING METHODS

"A": Set bar splicer assembly by means of a template bolt.
 "B": Set bar splicer assembly by nailing to wood forms or cementing to steel forms.
 (E) : Indicates epoxy coating.



STANDARD MECHANICAL SPLICER

Location	Bar size	No. assemblies required



BAR SPLICER ASSEMBLY FOR #5 BAR ON STUB ABUTMENTS

No. required =

NOTES

Splicer bars shall be deformed with threaded ends and have a minimum 60 ksi yield strength.
 All reinforcement shall be lapped and tied to the splicer bars.
 Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars. See Section 508 of the Standard Specifications.
 See approved list of bar splicer assemblies and mechanical splicers for alternatives.

Added 10-29-13

BSD-1

8-31-12

DESIGNED - RAY AHANCHI	EXAMINED - <i>James F. Jelliffe</i>	DATE - OCTOBER 1, 2013
CHECKED - AL-BARRAE R. SHEBIB	ACTING ENGINEER OF BRIDGE DIVISION	
DRAWN - MICHAEL B. MOSSMAN	PASSED - <i>Carl Lopez</i>	REVISED -
CHECKED - G.R.A. / A.R.S.	ACTING ENGINEER OF BRIDGES AND STRUCTURES	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS
STRUCTURE NO. 050 - 2651

SHEET NO. 10 OF 11 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(4)BR-1	LASALLE	38	27
CONTRACT NO. 66813			ILLINOIS FED. AID PROJECT	

