SI = SPECIALTY ITEM

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
					FED 80% STATE 20%	FED 80% STATE 20%	FED 80% STATE 20%	FED 80% STATE 20%	FED 80% STATE 20%	CITY 100%	CITY 100%	FED 80% STATE 20%	CITY 100%
					ROADWAY	ROADWAY	ROADWAY	BRIDGE	BRIDGE	HIGHWAY LIGHTING	TRAFFIC SIGNALS	TRAFFIC SIGNALS	CITY
					0003	0003	0003	0010	0010	0021	0021	0021	0043
					URBAN GRUNDY	RURAL GRUNDY	RURAL KENDALL	SN 032-0122	SN 032-0123	URBAN	PROLOGIS	GRANVILLE	URBAN
								GRUNDY	GRUNDY				
	X6026056	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	5	3								2
	X6026057	SANITARY MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1								
	X6026632	VALVE BOXES TO BE REMOVED	EACH	15	15								
	X6061100	CONCRETE MEDIAN, TYPE SB (SPECIAL)	SQ FT	15826	15826								
	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.4	0.3	0.3						
SI	X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	96169	69939	20373	5857						
SI	X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	12038	9268	2571	199						
SI	X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	12686	10626	1701	359						
SI	X8410102	TEMPORARY LIGHTING SYSTEM	L SUM	1			1						
SI	X8410118	MAINTENANCE OF TEMPORARY LIGHTING SYSTEM	L SUM	1			1						
SI	X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1								1	
SI	X8570231	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1							1		
SI	X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1370							801	569	
SI	X8860100	LOOP DETECTOR TESTING	EACH	2							1	1	

14

FILE NAME =	USER NAME = bdeoreno	DESIGNED - LDZ	REVISED -
V:\3195\66B83 (South Section)\CADD Sheets\D366B83-sht-SQ0-27.dgn		DRAWN - SRH/RMD	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED - DJD	REVISED -
SHT_PLAN	PLOT DATE = 8/6/2013	DATE - 7/15/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL. RTE. 47
SUMMARY OF QUANTITIES

SCALE: N/A | SHEET 27 OF 30 SHEETS | STA. N/A TO STA. N/A

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(11)DR, BR & BR-1	GRUNDY	644	30

CONTRACT NO. 66B83

ILLINOIS FED. AID PROJECT