

SCHEDULES OF QUANTITIES

RIP RAP

LOCATION	STATION	TO	STATION	OFFSET	LENGTH (FEET)	WIDTH (FEET)	FILTER FABRIC 28200200 (SQ YD)	STONE RIPRAP CLASS A4 28100107 (SQ YD)	STONE RIPRAP CLASS A4 (TONS)	BEDDING STONE (TONS)
MEDIAN DITCH	43+00.		44+05.	RT	105.0	16.2	189.0	189.0	126	57
SW APPROACH SN 057-0253	53+76.7		53+82.7	RT	6.0	17.4	11.6	11.6	8	3
SW APPROACH SN 057-0251	59+28.9		59+34.9	CL	6.0	19.0	12.7	12.7	8	4
MEDIAN DITCH	61+00.		64+50.	CL	350.0	16.2	630.0	630.0	420	189
TOTALS =							843.3	843.3	562	253
ROUND TO:							850.0	850.0		

NOTES:

1. STONE RIPRAP AND BEDDING STONE TONNAGE QUANTITIES ARE ESTIMATES AND FOR INFORMATION ONLY.
2. STONE RIPRAP IS ESTIMATED BASED ON 1.5 TONS PER CU YD.
3. BEDDING STONE IS ESTIMATED BASED ON 1.8 TONS PER CU YD.

HMA SURFACE REMOVAL

LOCATION	STATION	TO	STATION	LENGTH (FEET)	HOT-MIX ASPHALT SURFACE REMOVAL AREA TAKEN FROM CADD (SQ FT)	HOT-MIX ASPHALT SURFACE REMOVAL, BUTT JOINT 40600982 (SQ YD)
I-55 NBDL SHLD	32+60.00		32+95.00	35.0	320.8	35.6
I-55 NBDL SHLD	64+48.00		65+00.00	52.0	511.3	56.8
I-55 NBPL SHLD	32+60.00		32+95.00	35.0	196.2	21.8
I-55 NBPL SHLD	64+48.00		65+00.00	52.0	278.5	30.9
I-55 SBDL SHLD	29+00.00		29+35.00	35.0	347.8	38.6
I-55 SBDL SHLD	63+52.00		65+00.00	148.0	1417.0	157.4
I-55 SBPL SHLD	29+00.00		29+35.00	35.0	162.9	18.1
I-55 SBPL SHLD	63+52.00		65+00.00	148.0	880.6	97.8
LT. SHLD RAMP E	25+20.00		26+00.00	80.0	469.9	52.2
RT. SHLD RAMP E	25+20.00		26+00.00	80.0	329.4	36.6
LT. SHLD RAMP F	17+72.00		23+00.00	528.0	2206.6	245.2
RT. SHLD RAMP F	17+72.00		23+00.00	528.0	3176.0	352.9
LT. SHLD RAMP J	1007+00.00		1008+46.00	146.0	620.4	68.9
RT. SHLD RAMP J	1007+00.00		1008+46.00	146.0	959.4	106.6
RT. SHLD RAMP N	6+00.00		6+65.00	65.0	323.6	36.0
LT. SHLD RAMP N	6+77.00		7+42.00	65.0	260.0	28.9
LT. SHLD RAMP M	37+44.28		37+79.28	35.0	103.6	11.5
RT. SHLD RAMP M	37+44.28		37+79.28	35.0	213.5	23.7
SUB TOTAL SHLDS:						1419.7

HMA SURFACE REMOVAL SUMMARY

LOCATION	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" 44000155 (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL, BUTT JOINT 40600982 (SQ YD)
I-55 NBDL	1442.2	370.8
I-55 NBPL	1279.7	376.3
I-55 SBDL	2029.3	580.4
I-55 SBPL	1771.1	580.8
I-55 NBDL SHLD		92.5
I-55 NBPL SHLD		52.7
I-55 SBDL SHLD		196.1
I-55 SBPL SHLD		115.9
RAMP E		244.5
RAMP F		1047.7
RAMP J		480.9
RAMP M	344.2	60.8
RAMP N	323.0	885.6
RAMP E SHLD		88.8
RAMP F SHLD		598.1
RAMP J SHLD		175.5
RAMP M SHLD		35.2
RAMP N SHLD		64.8
TOTAL =	7189.5	6047.6
ROUND TO:	7190.0	6050.0

HMA SURFACE REMOVAL (CONTINUED)

LOCATION	STATION	TO	STATION	LENGTH (FEET)	HOT-MIX ASPHALT SURFACE REMOVAL AREA TAKEN FROM CADD (SQ FT)	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" 44000155 (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL, BUTT JOINT 40600982 (SQ YD)
RAMP E	24+72.00		26+00.00	128.0	2200.8		244.5
RAMP F	17+19.00		23+00.00	581.0	9429.1		1047.7
RAMP J	1007+00.00		1009+62.00	262.0	4328.2		480.9
RAMP M	35+61.15		36+11.37	50.2	842.9	93.7	
RAMP M	36+11.37		36+61.59	50.2	863.4	95.9	
RAMP M	36+61.59		37+11.80	50.2	843.4	93.7	
RAMP M	37+11.80		37+44.28	32.5	548.1	60.9	
RAMP M	37+44.28		37+79.28	35.0	547.4		60.8
RAMP N	21+24.00		24+62.00	338.0	5689.4		632.2
RAMP N	24+62.00		24+82.12	20.1	303.3	33.7	
RAMP N	24+82.12		25+33.39	51.3	715.1	79.5	
RAMP N	25+33.39		25+84.65	51.3	666.4	74.0	
RAMP N	25+84.65		26+35.89	51.2	628.7	69.9	
RAMP N	26+35.89		26+87.12	51.2	593.0	65.9	
RAMP N	6+00.00		7+42.00	142.0	2281.1		253.5
SUB TOTAL RAMPS:						667.1	2719.6

PATCHING

STATION	TO	STATION	ROUTE	LANE	LENGTH (FT)	WIDTH (FT)	SUBBASE GRAN. MATL., TYPE B 4" 31101200 (SQ YD)	CLASS D PATCHES, TYPE II, 10 INCH 44201765 (SQ YD)	CLASS D PATCHES, TYPE IV, 10 INCH 44201771 (SQ YD)
635+01.65		636+56.65	I-74	WBPS	155.0	6.0	103.3	0.0	103.3
637+75.		639+25.	I-74	EBPS	150.0	6.0	100.0	0.0	100.0
637+80.		639+30.	I-74	EBDS	150.0	6.0	100.0	0.0	100.0
50+76.29		50+88.29	I-55B	NBPS	12.0	6.0	8.0	8.0	0.0
56+40.05		56+52.05	I-55B	SBDS	12.0	6.0	8.0	8.0	0.0
TOTALS =							319.3	16.0	303.3
ROUND TO:							320.0	16.0	305.0