

# SCHEDULES OF QUANTITIES

## HOT-MIX ASPHALT & SHOULDERS (SHEET 13 OF 17)

LOCATION	STATION	TO	STATION	LENGTH (FOOT)	BITUMINOUS MATERIALS (PRIME COAT) 40600100 (GAL)	POLYMERIZED LEVELING BINDER (MACHINE METHOD) AVG. END AREA FROM CADD (SQ FT)	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-9.5, FG, N90 40600909 (TON)	HOT-MIX ASPHALT BINDER AVG. END AREA FROM CADD (SQ FT)	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90 40603092 (TON)	POLYMERIZED BINDER AVG. END AREA FROM CADD (SQ FT)	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90 40603243 (TON)	SURFACE AVG. END AREA FROM CADD (SQ FT)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 40603545 (TON)
RAMP N	14+00.00		14+50.00	50.00	26.8			11.2	41.9	3.1	11.6	2.7	10.1
RAMP N	14+50.00		15+00.00	50.00	26.8			11.2	41.9	3.1	11.6	2.7	10.1
RAMP N	15+00.00		15+50.00	50.00	26.8			11.2	41.9	3.1	11.6	2.7	10.1
RAMP N	15+50.00		15+81.71	31.71	19.4			11.9	28.3	3.3	7.8	2.9	6.8
RAMP N	15+81.71		16+42.00	60.29	32.0			12.5	56.2	3.5	15.6	3.0	13.6
RAMP N	16+42.00		16+99.92	57.92	31.2			12.1	52.5	3.4	14.6	2.9	12.7
RAMP N	16+99.92		17+55.96	56.04	29.3			11.9	49.7	3.3	13.8	2.9	12.0
RAMP N	17+55.96		18+10.50	54.54	29.0			11.7	47.5	3.2	13.1	2.8	11.4
RAMP N	18+10.50		18+63.88	53.38	28.4			11.5	45.8	3.2	12.7	2.8	11.0
RAMP N	18+63.88		19+16.38	52.50	27.9			19.3	75.8	3.1	12.3	2.7	10.7
RAMP N	19+16.38		19+68.32	51.94	27.6			22.5	87.2	3.1	12.1	2.7	10.5
RAMP N	19+68.32		20+19.94	51.62	24.9			14.6	56.4	3.1	12.0	2.7	10.4
RAMP N	20+19.94		20+44.00	24.06	12.9			11.6	20.8	3.1	5.6	2.7	4.8
RAMP N	20+44.00		20+71.42	27.42	9.7					9.9	20.2	2.7	5.5
RAMP N	20+71.42		20+88.00	16.58	5.9					9.9	12.2	2.7	3.3
RAMP N	20+88.00		21+22.83	34.83	12.3	7.5	19.5					2.7	7.0
RAMP N	21+22.83		21+74.20	51.37	18.2	6.4	24.7					2.7	10.3
RAMP N	21+74.20		22+25.56	51.36	19.2	5.1	19.7					2.8	10.8
RAMP N	22+25.56		22+76.90	51.34	19.7	4.2	16.1					2.9	11.1
RAMP N	22+76.90		23+28.23	51.33	18.9	2.9	11.3					2.8	10.7
RAMP N	23+28.23		23+79.54	51.31	18.1	2.0	7.6					2.7	10.2
RAMP N	23+79.54		24+30.84	51.30	17.8	1.7	6.4					2.7	10.2
RAMP N	24+30.84		24+82.12	51.28	17.4	1.7	6.3					2.6	10.1
SUB TOTALS RAMP N:					892.8		111.5		1269.2		381.0		384.2
RAMP M													
RAMP M	37+44.28		37+62.29	18.01	5.9	1.5	2.0					2.5	3.3
RAMP M	37+62.29		37+79.28	16.99	6.3	1.5	1.9					2.5	3.1
SUB TOTALS RAMP M:					12.2		4.0						6.4
SUB TOTAL =					2317.1		115.5		3216.1		1097.9		993.1

\*SHOWN FOR INFORMATION ONLY