

SCHEDULES OF QUANTITIES

HOT-MIX ASPHALT & SHOULDERS (SHEET 17 OF 17)

HOT-MIX ASPHALT & SHOULDER SUMMARY

LOCATION	BITUMINOUS MATERIALS (PRIME COAT) 40600100 (GAL)	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-9.5, FG, N90 40600909 (TON)	HMA BINDER COURSE, IL-19.0, FG, N90 40603092 (TON)	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90 40603243 (TON)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 40603545 (TON)	AGGREGATE SHOULDER, TYPE A 6" 48100500 (SQ YD)	AGGREGATE SHOULDER, TYPE A 8" 48100700 (SQ YD)	*AGGREGATE SHOULDERS (TON)	HOT MIX ASPHALT SHOULDER 48203100 (TON)
I-55 NBDL	1191.0	137.7	1263.5	367.6	532.7				
I-55 NBPL	922.3	101.5	806.8	291.3	412.7				
I-55 SBDL	1298.5	203.8	965.0	341.2	621.2				
I-55 SBPL	981.5	144.8	743.0	276.6	467.0				
I-55 NBDL SHLD	214.9					504.1		174.5	1023.3
I-55 NBPL SHLD	172.4					609.1		249.6	683.7
I-55 SBDL SHLD	228.3					513.0		194.9	526.6
I-55 SBPL SHLD	192.9					684.5		289.2	751.2
RAMP E	445.5		440.4	199.6	174.8				
RAMP F	589.1		926.8	299.8	258.0				
RAMP J	377.5		579.7	217.5	169.7				
RAMP N	892.8	111.5	1269.2	381.0	384.2				
RAMP M	12.2	4.0			6.4				
RAMP E SHLD	79.0					292.5		111.0	372.3
RAMP F SHLD	138.9					533.0		220.8	752.5
RAMP J SHLD	85.6					327.7		116.9	486.1
RAMP N SHLD	174.8					325.8	368.4	274.8	858.0
RAMP M SHLD	3.5					56.5		19.3	4.0
I-74 EB						177.8		53.1	
I-74 WB						155.6		48.1	
TOTALS:	8000.7	703.3	6994.3	2374.6	3026.7	4179.6	368.4	1752.0	5457.7
ROUND TO:	8010.0	710.0	7000.0	2380.0	3030.0	4180.0	370.0		5460.0

*SHOWN FOR INFORMATION ONLY