

SCHEDULES OF QUANTITIES

TEMPORARY CONCRETE BARRIER WALL

TEMPORARY CONCRETE BARRIER 70400100						
ROADWAY	LANE	STAGE	STATION	TO	STATION	LENGTH
FAP 704	SOUTHBOUND	1	47+25		60+80	1,340.0
FAP 704	NORTHBOUND	1	46+50		62+15	1,590.0
FAI 74	WBDL	1A	634+70		637+40	270.0
FAI 74	WBPL	1A	634+90		637+40	250.0
FAI 74	EBDL	1A	637+10		639+30	220.0
FAI 74	EBPL	1A	637+10		639+30	220.0
TOTAL =						3,890.0

TEMPORARY CONCRETE BARRIER WALL (CONTINUED)

IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 70600350					
ROADWAY	LANE	STAGE	STATION	#	EACH
FAI 74	WESTBOUND	1B	637+40	2.0	
FAI 74	EASTBOUND	1B	637+10	2.0	
FAI 74	WESTBOUND	2A	637+40	2.0	
FAI 74	EASTBOUND	2A	637+10	2.0	
FAI 74	WESTBOUND	2B	637+40	2.0	
FAI 74	EASTBOUND	2B	637+10	2.0	
TOTAL =					12.0

IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE, NARROW), TEST LEVEL 3 70600352				
ROADWAY	LANE	STAGE	STATION	# EACH
FAP 704	NORTHBOUND	2	62+15	1.0
FAP 704	SOUTHBOUND	2	47+25	1.0
TOTAL =				2.0

RELOCATE TEMPORARY CONCRETE BARRIER 70400200						
ROADWAY	LANE	STAGE	STATION	TO	STATION	LENGTH
FAP 704	SOUTHBOUND	2	47+25		60+80	1,340.0
FAP 704	NORTHBOUND	2	46+50		62+15	1,590.0
FAI 74	WBDL	1B	634+70		637+40	270.0
FAI 74	WBPL	1B	634+90		637+40	250.0
FAI 74	EBDL	1B	637+10		639+30	220.0
FAI 74	EBPL	1B	637+10		639+30	220.0
FAI 74	WBDL	2A	634+70		637+40	270.0
FAI 74	WBPL	2A	634+90		637+40	250.0
FAI 74	EBDL	2A	637+10		639+30	220.0
FAI 74	EBPL	2A	637+10		639+30	220.0
FAI 74	WBDL	2B	634+70		637+40	270.0
FAI 74	WBPL	2B	634+90		637+40	250.0
FAI 74	EBDL	2B	637+10		639+30	220.0
FAI 74	EBPL	2B	637+10		639+30	220.0
TOTAL =						5,810.0

BARRIER WALL MARKER, TYPE C

LOCATION/DESCRIPTION	LENGTH (FOOT)	BARRIER WALL MARKER, TYPE C 78200530 EACH
S.N. 057-0254 SBDS PARAPET WALL	204.50	2.0
S.N. 057-0252 SBDS PARAPET WALL	183.00	2.0
S.N. 057-0254 SBPS PARAPET WALL	204.50	3.0
S.N. 057-0252 SBPS PARAPET WALL	183.00	1.0
S.N. 057-0253 NBDS PARAPET WALL	204.50	2.0
S.N. 057-0251 NBDS PARAPET WALL	183.00	2.0
S.N. 057-0253 NBPS PARAPET WALL	204.50	1.0
S.N. 057-0251 NBPS PARAPET WALL	183.00	2.0
TOTAL =		15.0
ROUND TO:		15.0

OVERHEAD SIGN STRUCTURES

ROADWAY	EXISTING SIGN STRUCTURE NUMBER	PROPOSED SIGN STRUCTURE NUMBER	SIGN	72000300 SIGN PANEL - TYPE 3 (SQ FT)	72400330 REMOVE SIGN PANEL - TYPE 3 (SQ FT)	73304000 OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED (FOOT)	73600100 REMOVE OVERHEAD SIGN STRUCTURE - SPAN (EACH)	73600200 REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER (EACH)	73700300 REMOVE CONCRETE FOUNDATION - OVERHEAD (EACH)
I-74 EB	5 S 057 I074 R133.90	5 B 057 I074 R133.90	A	152.00	160.0	45.5	1.0	0.0	4.0
			B	143.75	124.5				
			C	200.00	211.0				
I-74 WB	5 C 057 I074 L133.90	5 B 057 I074 L133.90	D	150.00	151.0	15.0	0.0	1.0	1.0
TOTALS:				645.75	646.5	60.5	1.0	1.0	5.0
ROUND TO:				646.00	650.0	60.5	1.0	1.0	5.0

IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 70600250					
ROADWAY	LANE	STAGE	STATION	#	EACH
FAI 74	WESTBOUND	1A	637+40	2.0	
FAI 74	EASTBOUND	1A	637+10	2.0	
TOTAL =					4.0

IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE, NARROW), TEST LEVEL 3 70600251					
ROADWAY	LANE	STAGE	STATION	#	EACH
FAP 704	NORTHBOUND	1	62+15	1.0	
FAP 704	SOUTHBOUND	1	47+25	1.0	
TOTAL =					2.0

SURVEY MARKERS

	STATION	OFFSET	XZ193300 SURVEY MARKER TYPE 1 (SPECIAL) (EACH)	XZ193400 SURVEY MARKER TYPE 2 (SPECIAL) (EACH)
SOUTHBOUND VETERAN'S PARKWAY				
POC #300	58+98.61	0.0'	1	0
NORTHBOUND VETERAN'S PARKWAY				
POT #47	59+00.00	0.0'	0	1
TOTALS:			1	1