


STATION	TO	STATION	ROUTE	LANE	LENGTH MEAS. FROM CADD (FT)	FROM EOS OUT WIDTH (FT)	BASE COURSE (OPTION) Z0002900 (SQ YD)
①	1007+25.	1013+50.3	RAMP J	PS	671.9	2.0	149.3
②	1008+50.	1012+00.	RAMP J	DS	340.5	2.0	75.7
③	1012+00.	1012+50.	RAMP J	DS	49.0	3.0	16.3
④	1012+50.	1013+50.	RAMP J	DS	98.6	4.0	43.8

CONTINUED ON SHEET #138 AS ①

CONTINUED ON SHEET #138 AS ④

MATCHLINE STA. 1013+00.00
RAMP J (SEE SHEET #138)

PLAN SHEET LOCATION



BASE COURSE (OPTION)

NOTE: THIS WORK SHALL BE PLACED ON THE OUTSIDE OF THE EXISTING SHOULDERS BEFORE HMA PAVING OPERATIONS. SLOPES ARE SHOWN IN THE X-SECTIONS.

FILE NAME =	USER NAME = detersbj	DESIGNED -	REVISED -
c:\pwork\pwork\pwork\detersbj\d0157116\0570570-sht-plan.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

BASE COURSE (OPTION) PLAN SHEET			
RAMP J			
SCALE:	SHEET 1	OF 1	SHEETS
	STA. 1006+00.00 TO STA. 1013+00.00		

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
704	57-20(HB,HB-1)BR-1	MCLEAN	440	142
CONTRACT NO. 70570				
ILLINOIS FED. AID PROJECT				