

| | | | | | |
|-------------------------|--------------------------|--------------------------------|--------------------------------|--------------------------------|--------------------------------|
| LOCATION OF WORK: | <i>FAI 74</i> | S.N. 057-0251 | S.N. 057-0252 | S.N. 057-0253 | S.N. 057-0254 |
| | URBAN MULTILANE | URBAN MULTILANE | URBAN MULTILANE | URBAN MULTILANE | URBAN MULTILANE |
| | OTHER PRINCIPAL ARTERIAL | OTHER PRINCIPAL ARTERIAL | OTHER PRINCIPAL ARTERIAL | OTHER PRINCIPAL ARTERIAL | OTHER PRINCIPAL ARTERIAL |
| | STA. 29+00 TO STA. 65+00 | STA. 57+19.05 TO STA. 58+99.57 | STA. 57+12.20 TO STA. 58+97.86 | STA. 51+55.69 TO STA. 53+56.48 | STA. 51+14.85 TO STA. 53+23.26 |
| | MCLEAN COUNTY | MCLEAN COUNTY | MCLEAN COUNTY | MCLEAN COUNTY | MCLEAN COUNTY |
| FUNDING BREAKOUT: | 90% FEDERAL, 10% STATE | 90% FEDERAL, 10% STATE | 90% FEDERAL, 10% STATE | 90% FEDERAL, 10% STATE | 90% FEDERAL, 10% STATE |
| CONSTRUCTION TYPE CODE: | 0004 | 0011 | 0011 | 0011 | 0011 |

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | | | | | | |
|--------------------------|--|-------|----------------|----------|-----|-----|-----|-----|-----|
| 73600200 | REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER | EACH | 1.0 | 1.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 73700300 | REMOVE CONCRETE FOUNDATION - OVERHEAD | EACH | 5.0 | 5.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| • 78003110 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4" | FOOT | 1,490.0 | 1,490.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| • 78009004 | MODIFIED URETHANE PAVEMENT MARKING - LINE 4" | FOOT | 23,650.0 | 23,650.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| • 78009008 | MODIFIED URETHANE PAVEMENT MARKING - LINE 8" | FOOT | 2,990.0 | 2,990.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| • 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 270.0 | 270.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| • 78100105 | RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) | EACH | 30.0 | 0.0 | 6.0 | 8.0 | 8.0 | 8.0 | 8.0 |
| • 78200410 | GUARDRAIL MARKERS, TYPE A | EACH | 105.0 | 105.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| • 78200530 | BARRIER WALL MARKERS, TYPE C | EACH | 15.0 | 0.0 | 4.0 | 3.0 | 3.0 | 3.0 | 5.0 |
| • 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 13.0 | 13.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 3,150.0 | 3,150.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 270.0 | 270.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| • 80400100 | ELECTRIC SERVICE INSTALLATION | EACH | 1.0 | 1.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| • 81028200 | UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA. | FOOT | 10.0 | 10.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| • DENOTES SPECIALTY ITEM | | | | | | | | | |

| | | | | | | | | | | | | | |
|---|-----------------------------|------------|-----------|---|--|--|--|--|--------------------|-------------------|--------|-----------------|--------------|
| FILE NAME : | USER NAME : detarsbj | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | | | | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| c:\pvc\work\pvidot\detarsbj\d0197116\0578 | 78-ant-500.dgn | DRAWN - | REVISED - | | | | | | 704 | 57-201HB,HB-1BR-1 | MCLEAN | 440 | 14 |
| #MODELNAME# | PLOT SCALE = 48.0000' / in. | CHECKED - | REVISED - | | SCALE: SHEET 9 OF 13 SHEETS STA. TO STA. | | | | CONTRACT NO. 70570 | | | | |
| | PLOT DATE = 8/13/2013 | DATE - | REVISED - | | ILLINOIS FED. AID PROJECT | | | | | | | | |

14