

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				FEDERAL FUNDS		
				80% FED / 20% STATE		
				RURAL ROADWAY	RURAL BRIDGE	URBAN BRIDGE
			0004	0011	0014	
			IL 48	IL 48	IL 29	
44000100	PAVEMENT REMOVAL	SQ YD	185	185		
44000152	HOT MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	2,065	2,065		
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	80	80		
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ YD	44	44		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	104	104		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	186	186		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1	
50200100	STRUCTURE EXCAVATION	CU YD	313		313	
50300100	FLOOR DRAINS	EACH	12		12	
50300225	CONCRETE STRUCTURES	CU YD	172.6		172.6	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	368.9		368.9	
50300260	BRIDGE DECK GROOVING	SQ YD	902		902	
50300300	PROTECTIVE COAT	SQ YD	1,132		1,132	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	

design firm
no. 184001036



USER NAME * gjameson	DESIGNED -	REVISED
FILE NAME * 0672461-SHT-SUM.dgn	CHECKED -	REVISED
PLOT SCALE * 10.0000 / IN.	DRAWN -	REVISED
PLOT DATE * 0/16/2013	CHECKED -	REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES
IL 29 OVER IL 48 / IL 48 OVER BEAR CREEK

SCALE: NTS SHEET 3 OF 7 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	(4)1, 136B-1	CHRISTIAN	97	6
* 75(IL 29) & 714(IL 48)			CONTRACT NO. 72A61	
ILLINOIS FED. AID PROJECT				