

LOCATION		OFFSET	LENGTH	WIDTH	AREA	THICKNESS	48102100 AGGREGATE WEDGE SHOULDER, TYPE B
STATION	STATION		(FOOT)	(FOOT)	(SQ FT)	(INCHES)	(TON)
IL 48 OVER BEAR CREEK							
STAGE III							
621+50.00	621+80.00	LT	30.00	4.00	120.00	1.25	1
621+80.00	623+05.00	LT	125.00	4.00	500.00	1.75	6
623+05.00	623+25.00	LT	20.00	4.00	80.00	2.25	2
623+25.00	623+65.00	LT	40.00	4.00	160.00	2.25	3
623+65.00	625+59.00	LT	194.00	4.00	776.00	3.25	16
621+50.00	621+80.00	RT	30.00	4.00	120.00	1.25	1
621+80.00	623+05.00	RT	125.00	4.00	500.00	1.75	6
623+05.00	623+25.00	RT	20.00	4.00	80.00	2.25	2
623+25.00	625+78.00	RT	253.00	4.00	1012.00	3.25	21
628+25.00	629+75.00	LT	150.00	4.00	600.00	3.25	13
629+75.00	630+75.00	LT	100.00	4.00	400.00	1.75	5
630+75.00	630+96.00	LT	21.00	4.00	84.00	1.25	1
630+96.00	632+20.00	LT	124.00	4.00	496.00	1.25	4
632+20.00	632+50.00	LT	30.00	4.00	120.00	1.25	1
628+44.00	629+75.00	RT	131.00	4.00	524.00	3.25	11
629+75.00	630+75.00	RT	100.00	4.00	400.00	1.75	5
630+75.00	630+96.00	RT	21.00	4.00	84.00	1.25	1
630+96.00	632+20.00	RT	124.00	4.00	496.00	1.25	4
632+20.00	632+50.00	RT	30.00	4.00	120.00	1.25	1
TOTALS							104

LOCATION	OFFSET	TOTAL AREA	28100107 STONE RIPRAP, CLASS A4	28100109 STONE RIPRAP, CLASS A5	28200200 FILTER FABRIC
		SQ FT	(SQ YD)	(SQ YD)	(SQ YD)
IL 48 OVER BEAR CREEK					
STA. 624+90 TO STA. 625+85	LT	3,032	337		337
STA. 625+85 TO STA. 627+95	LT	13,372		1,486	1,486
STA. 627+95 TO STA. 629+60	LT	5,729	637		637
STA. 624+40 TO STA. 626+06	RT	3,878	431		431
STA. 626+06 TO STA. 628+16	RT	11,892		1,322	1,322
STA. 628+16 TO STA. 629+60	RT	3,402	378		378
SUBTOTAL			1,783	2,808	4,591
IL 29 OVER IL 48					
SUBTOTAL			113		197
TOTALS			1,896	2,808	4,788

LOCATION			TYPE	COLOR	70300100 SHORT TERM PAVEMENT MARKING	70300230 TEMPORARY PAVEMENT MARKING - LINE 5"	70300280 TEMPORARY PAVEMENT MARKING - LINE 24"	70301000 WORK ZONE PAVEMENT MARKING REMOVAL	78001120 PAINT PAVEMENT MARKING - LINE 5"	78100100 RAISED REFLECTIVE PAVEMENT MARKER	78300100 PAVEMENT MARKING REMOVAL	78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
STATION	STATION	OFFSET			(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(FOOT)	(EACH)	(SQ FT)	(EACH)
STAGE 1												
621+50	626+22	CL										6
621+80	632+20	LT	SOLID	YELLOW		1,040		434			434	
621+80		RT	SOLID	WHITE			12					
621+80	624+50	CL	SKIP DASH	YELLOW							30	
621+90	632+20	RT	SOLID	YELLOW		1,032		430			430	
627+79	632+50	CL										6
629+50	632+20	CL	SKIP DASH	YELLOW							30	
632+20		LT	SOLID	WHITE			12					
STAGE 2												
621+80	632+20	LT	SOLID	YELLOW		1,042		433				
621+80	632+20	RT	SOLID	YELLOW		1,040		433				
621+80		RT	SOLID	WHITE				24				
632+20		LT	SOLID	WHITE				24				
STAGE 3 (ASSUME THREE APPLICATIONS)												
621+80	632+20	LT	SOLID	WHITE	312			35				
621+80	632+20	CL	SKIP DASH	YELLOW	312			35				
621+80	632+20	RT	SOLID	WHITE	312			35				
FINAL PAVEMENT MARKING												
621+50	632+50	LT	SOLID	WHITE					1,100			
621+50	632+50	CL	SKIP DASH	YELLOW					280			
621+50	632+50	RT	SOLID	WHITE					1,100			
621+50		CL								1		
622+30		CL								1		
623+10		CL								1		
623+90		CL								1		
624+70		CL								1		
625+50		CL								1		
628+70		CL								1		
629+50		CL								1		
630+30		CL								1		
631+10		CL								1		
631+90		CL								1		
SUBTOTAL					936	4,154	24	1,883	2,480	11	924	12

LOCATION		OFFSET	28000400 PERIMETER EROSION BARRIER
STATION	STATION		(FOOT)
IL 48 OVER BEAR CREEK			
628+70.00	629+60.00	LT	94
TOTALS			94

LOCATION		LENGTH	WIDTH	AREA	42001430 BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	42001500 P.C. CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT
STATION	STATION	(FOOT)	(FOOT)	(SQ FT)	(SQ YD)	(SQ YD)
IL 48 OVER BEAR CREEK						
625+68.00	625+81.00	13.00	24.00	312.00	35	
625+68.00	625+81.00	13.00	6.92	89.96		10
625+68.00	625+81.00	13.00	6.92	89.96		10
628+21.00	628+34.00	13.00	24.00	312.00	35	
628+21.00	628+34.00	13.00	6.92	89.96		10
628+21.00	628+34.00	13.00	6.92	89.96		10
TOTALS					70	40

design firm
no. 184001036



USER NAME : g.jameson
FILE NAME : 0672AG1-SHT-SCHEDULE
PLOT SCALE : 1/8" = 1'-0"
PLOT DATE : 01/28/2013

DESIGNED -
CHECKED -
DRAWN -
CHECKED -

REVISED
REVISED
REVISED
REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
IL 29 OVER IL 48 / IL 48 OVER BEAR CREEK

SCALE: NTS SHEET 3 OF 4 SHEETS STA. TO STA.

F.A.P.
RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.
* (4) 136B-1 CHRISTIAN 97 13
* 75(IL 29) & 714(IL 48) CONTRACT NO. 72A61
ILLINOIS FED. AID PROJECT