

PAVING SCHEDULE

LOCATION	STATION	TO	STATION	LENGTH (FT)	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT) (TON)	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90 (TON)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 (TON)	HMA BASE COURSE, 10" (SQ YD)	HMA SHOULDERS (TON)	SHOULDER RUMBLE STRIP (FT)	AGGREGATE WEDGE SHOULDER, TYPE B (TON)	HMA SURFACE REMOVAL - BUTT JOINT (SY)	TEMPORARY RAMP (SY)
TR 420 RAMP A													
RAMP PVT	100+00.00	TO	103+02.30	302	0.10	34	23						
	103+02.30	TO	119+42.20	1,640	1.11	367	245					30	30
OUTSIDE SHLD	100+00.00	RT	106+62.41	RT	662	0.28			82		45		
	106+62.41	RT	119+42.20	RT	1,280	0.32			96		87		
INSIDE SHLD	103+02.30	LT	106+62.41	LT	360	0.06			45				
	106+62.41	LT	119+42.20	LT	1,280	0.22			64		154		
TR 420 RAMP B													
RAMP PVT	201+37.60	TO	217+49.60	1,612	1.09	361	241					30	30
	217+49.60	TO	224+99.80	750	0.25	84	56						
OUTSIDE SHLD	201+37.60	RT	217+49.60	RT	1,612	0.41			120		110		
	217+49.60	RT	224+99.80	RT	750	0.32			93		51		
INSIDE SHLD	200+75.00	LT	217+49.60	LT	1,675	0.28			83		100		
	217+49.60	LT	224+99.80	LT	750	0.13			37				
TR 420 RAMP C													
RAMP PVT	300+00.00	TO	303+02.50	303	0.10	34	23						
	303+02.50	TO	317+93.20	1,491	1.01	334	223					30	30
OUTSIDE SHLD	300+00.00	RT	306+62.40	RT	662	0.28			82		45		
	306+62.40	RT	317+93.20	RT	1,131	0.29			84		77		
INSIDE SHLD	303+02.50	LT	306+62.40	LT	360	0.06			45				
	306+62.40	LT	317+93.20	LT	1,131	0.19			56		136		
TR 420 RAMP D													
RAMP PVT	401+39.70	TO	415+84.40	1,445	0.98	162	216					30	30
	415+84.40	TO	423+40.60	756	0.26	85	56						
OUTSIDE SHLD	401+39.70	RT	412+83.81	RT	1,144	0.29			85		103		
	412+83.81	RT	423+40.60	RT	1,057	0.45			132		951		
INSIDE SHLD	401+39.70	LT	411+77.20	LT	1,038	0.18			52		125		
	411+77.20	LT	415+84.40	LT	407	0.07			20				
TOTALS =					107.7	39,723	14,926	652	15,073	99,498	11,288	2,813	1,529

USER NAME = sparksgw PLOT SCALE = 2.0000' / in. PLOT DATE = Sep-06-2013 07:47:04AM	DESIGNED - BTM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN - BTM	REVISED -		* (84-10-1)RS-3, (84-10-2)RS-4	SANGAMON	194	24					
	CHECKED - JSA	REVISED -		CONTRACT NO. 72C90				ILLINOIS FED. AID PROJECT				
	DATE - 12/19/12	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.				