


EXIST. CURVE C2 (I-72)
 PI STA. = 80+04.14
 $\Delta = 21^\circ 00' 50''$ (RT)
 $D = 1^\circ 00' 00''$
 $R = 5,729.58'$
 $T = 1,062.63'$
 $L = 2,101.39'$
 $E = 97.71'$
 $e = 3.34\%$
 $T.R. = 67.50'$
 $S.E. RUN = 150.00'$
 $P.C. STA. = 69+41.50$
 $P.T. STA. = 90+42.89$

PAVEMENT MARKING LEGEND

- ① PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 5" (30' SKIP, 10' DASH)
- ② PR URETHANE PAVEMENT MARKING, LINE 5" (SOLID YELLOW)
- ③ PR URETHANE PAVEMENT MARKING, LINE 5" (SOLID WHITE)
- ④ PR URETHANE PAVEMENT MARKING, LINE 6" (SOLID WHITE)
- ⑤ PR URETHANE PAVEMENT MARKING, LINE 6" (6' SKIP, 2' DASH)
- ⑥ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 8" (SOLID WHITE)
- ⑦ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 12" (SOLID WHITE)
- ⑧ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 24" (SOLID WHITE)
- ⑨ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LETTERS & SYMBOLS (SOLID WHITE)
- ▽ PR RAISED REFLECTIVE PAVEMENT MARKER, ONE-WAY, WHITE
- ◀ PR RAISED REFLECTIVE PAVEMENT MARKER, ONE-WAY, AMBER



USER NAME = sparksgw PLOT SCALE = 100.0000' / in. PLOT DATE = Sep-06-2013 07:53:01AM	DESIGNED - BTM DRAWN - BTM	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PLAN SHEETS			F.A.I. RTE. I-72 SECTION * COUNTY SANGAMON TOTAL SHEETS 194 SHEET NO. 34
	CHECKED - JSA DATE - 12/19/12	REVISED - REVISED -		SCALE:	SHEET NO. OF SHEETS STA. TO STA.	* (84-10-1)RS-3, (84-10-2)RS-4 ILLINOIS FED. AID PROJECT	