

DRAINAGE SCHEDULE															
LOCATION	STATION	TO	STATION	PIPE CULV REM (FOOT)	PLUG EXIST CULVERTS (EACH)	INLETS TO BE ADJUSTED (EACH)	FILLING INLETS (EACH)	FILLING EXIST CULVERTS (EACH)	REM INLET BOX (EACH)	STONE RIPRAP CL A4 (SQ YD)	FILTER FABRIC FOR RIPRAP (SQ YD)	TY D INLET BOX (STD 609006) (EACH)	METAL END SECTIONS, 12" (SQ FT)	TRENCH BACKFILL (CU YD)	PIPE CULV, CL A, TY 1, 12" (FOOT)
MECHANICSBURG RD. MAINLINE															
	95+24.80	RT					1								
	95+24.80	LT			1										
	98+38.40	LT								92	92	1	1		11
	98+49.13	RT								92	92	1	1		11
	98+69.50	LT						1							
	98+69.50	LT	TO	98+80.80	RT	60								11	
	98+80.80	RT						1							
	98+83.80	RT				1									
	101+35.40	LT							1						
	101+35.40	LT	TO	101+45.70	RT	60								11	
	101+45.70	RT							1						
	101+51.50	RT				1									
	101+66.88	LT								92	92	1	1		11
	101+77.54	RT								92	92	1	1		11
	104+80.20	LT					1								
	104+80.20	RT				1									
TR 420 MAINLINE															
	288+98.00	CL					1								
	294+27.70	LT			1		1								
	294+27.70	LT	TO	294+78.00	LT			1							
	294+78.00	LT					1								
	298+13.21	LT								92	92	1	1		11
	298+13.21	RT								92	92	1	1		11
	298+43.70	LT						1							
	298+43.70	LT	TO	298+40.80	RT	59								12	
	298+40.80	RT						1							
	298+45.20	RT				1									
	301+15.10	RT				1									
	301+16.40	LT							1						
	301+16.40	LT	TO	301+16.40	RT	57								12	
	301+16.40	RT						1							
	301+47.40	LT								92	92	1	1		11
	301+47.40	RT								92	92	1	1		11
	304+92.00	LT					1								
	304+93.00	LT	TO	305+30.50	LT										
	305+30.50	LT					1								
	305+30.50	RT				1									
	309+98.00	CL						1							
TOTALS =				236	8	2	6	2	8	736	736	8	8	46	88

USER NAME = sparksgw	DESIGNED - BTM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 2.0000' / in.	DRAWN - BTM	REVISED -					1722	*	SANGAMON	194	83
PLOT DATE = Sep-06-2013 09:11:15AM	CHECKED - JSA	REVISED -		SCALE:			SHEET NO. OF SHEETS STA. TO STA.			* (84-10-1RS-3,84-10-2RS-4)BR,I	
	DATE - 12/19/12	REVISED -								ILLINOIS FED. AID PROJECT	

FILE NAME = c:\pwwork\pwwork\sparksgw\d0359822\0672C90.sht.schedule.dgn

(84-10-1,2)RS-3 & (84-10-2)RS-4