


**NOTES:**

Following removal of HMA Surface, Contractor shall notify resident engineer to inspect & sound existing deck.

Quantities are estimated, actual quantities to be determined by the Resident Engineer.

Protective Shield shall be installed as directed by resident engineer to protect traffic below.

**PATCHING LEGEND**



**BILL OF MATERIAL**

Item	Unit	Total
Deck Slab Repair (Partial)	Sq. Yd.	50
Deck Slab Repair (Full Depth Type I)	Sq. Yd.	20
Deck Slab Repair (Full Depth Type II)	Sq. Yd.	10
Protective Shield	Sq. Yd.	313.0

Patch No.	Size	Deck Slab Repair (Part Depth)
PD1	EST	50
PD2		
PD3		
PD4		
PD5		
PD6		
PD7		
PD8		
PD9		
PD10		
PD11		
PD12		
PD13		
PD14		

Patch No.	Size	Deck Slab Repair (FD TY I)	Deck Slab Repair (FD TY II)
FD1	EST	20	10
FD2			
FD3			
FD4			
FD5			
FD6			
FD7			
FD8			
FD9			
FD10			
FD11			
FD12			
FD13			
FD14			

FILE NAME = Oak Crest Rd. over I-72.dgn	USER NAME =	DESIGNED - SAL	REVISED -
		CHECKED - MTH	REVISED -
		DRAWN - TJW	REVISED -
		CHECKED - MTH	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**DECK PATCHING PLAN  
OAK CREST RD. (TR-171) OVER F.A.I.-72 - S.N.084-0151**

SHEET NO. 6 OF 8 SHEETS

F.A.I. RTE. 72	SECTION	COUNTY SANGAMON	TOTAL SHEETS 194	SHEET NO. 145
• (84-10-1RS-3, 84-10-2RS-RIBR,I		CONTRACT NO. 72C90		
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT				