



Notes:
 Hatched area indicates Concrete Removal.
 Existing reinforcement bars extending into the new construction shall be cleaned, straightened and incorporated into the new construction. Cost included with Concrete Removal.
 Existing reinforcement bars not extending into the new construction shall be cut off and covered with a 2" layer of cement grout. Cost included with Concrete Removal.
 Elevations based off a datum difference of -0.49' from existing plans.

* Top of Curtain Wall shall be removed to expose the existing rebar to allow access for extension without damaging the existing reinforcement.

ELEVATION
 (N. Abut. Shown, S. Abut. Similar)

OUTSIDE ELEVATION OF CURTAIN WALL
 (Looking East)

SECTION B-B

FILE NAME TR420 over FAI-72.dgn	USER NAME =	DESIGNED - SAL	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CONCRETE REMOVAL, ABUTMENTS OVERPASS RD. (TR-420) OVER F.A.I.-72 - S.N. 084-0154	F.A.I. RTE. =	SECTION =	COUNTY =	TOTAL SHEETS =	SHEET NO. =
	PLOT SCALE =	DRAWN - TJW	REVISED -			72	*	SANGAMON	194	165
PLOT DATE =	CHECKED - MTH	REVISED -		SHEET NO. 18 OF 25 SHEETS		• (84-10-1RS-3, 84-10-2RS-R)B,R,I FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT CONTRACT NO. 72C90				