

SUMMARY OF QUANTITIES				CONSTRUCTION CODE					
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STATE					
				SN 093-0024					
				0011					
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	25	25					
20200100	EARTH EXCAVATION	CU YD	475	475					
20200200	ROCK EXCAVATION	CU YD	20	20					
20300100	CHANNEL EXCAVATION	CU YD	785	785					
20400800	FURNISHED EXCAVATION	CU YD	725	725					
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	52	52					
28000305	TEMPORARY DITCH CHECKS	FOOT	8	8					
28000400	PERIMETER EROSION BARRIER	FOOT	1,046	1,046					
28000500	INLET AND PIPE PROTECTION	EACH	4	4					
28200200	FILTER FABRIC	SQ YD	972	972					
28401600	SLOPE MATTRESS 18"	SQ YD	972	972					
35600724	HOT-MIX ASPHALT BASE COURSE WIDENING, 12"	SQ YD	371	371					
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	112	112					
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100	100					

*SPECIALTY ITEM



JOB # 2223.5
 FILE NAME # 0774217-sh1-soq.dgn
 PLOT SCALE # 20:8000 1/4" = 1'-0"
 PLOT DATE # 7/25/2013

DESIGNED - NAK
 DRAWN - TJD
 CHECKED - NAK
 DATE - 4/8/2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SBI RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1B	112A1B-1	WABASH	52	3
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 74217	