

SUMMARY OF QUANTITIES				CONSTRUCTION CODE					
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FEDERAL					
				20% STATE					
				SN 093-0024					
				0011					
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	191	191					
40600300	AGGREGATE (PRIME COAT)	TON	4	4					
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	47	47					
40600990	TEMPORARY RAMP	SQ YD	22	22					
40603085	HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N70	TON	287	287					
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	154	154					
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	35	35					
44000100	PAVEMENT REMOVAL	SQ YD	258	258					
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	696	696					
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1					
50105220	PIPE CULVERT REMOVAL	FOOT	18	18					
50200100	STRUCTURE EXCAVATION	CU YD	152	152					
50200300	COFFERDAM EXCAVATION	CU YD	24	24					
50201101	COFFERDAM (TYPE 1) (LOCATION - 1)	EACH	1	1					



J203 - 2/27/11
 FILE NAME = 0714217 sub1.spc.dwg
 PLOT SCALE = 28.0328 * 1 in.
 PLOT DATE = 7/27/2011

DESIGNED - NAK
 DRAWN - TJD
 CHECKED - NAK
 DATE - 4/8/2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SBI	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
18	112A1B-1	WABASH	52	4
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 74217	