

SUMMARY OF QUANTITIES				CONSTRUCTION CODE				
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STATE				
				SN 093-0024 0011				
50201102	COFFERDAM (TYPE 1) (LOCATION - 2)	EACH	1	1				
50300225	CONCRETE STRUCTURES	CU YD	179.5	179.5				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	201.8	201.8				
50300260	BRIDGE DECK GROOVING	SQ YD	425	425				
50300300	PROTECTIVE COAT	SQ YD	585	585				
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1				
50500505	STUD SHEAR CONNECTORS	EACH	1,920	1,920				
50800105	REINFORCEMENT BARS	POUND	23,320	23,320				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	73,410	73,410				
50800515	BAR SPLICERS	EACH	62	62				
50800530	MECHANICAL SPLICERS	EACH	60	60				
51500100	NAME PLATES	EACH	1	1				
51602000	PERMANENT CASING	FOOT	31.6	31.6				
51603000	DRILLED SHAFT IN SOIL	CU YD	21.2	21.2				