

TEMPORARY RAMP			
LOCATION	LENGTH	WIDTH	SQ YD
STA 115+40.00	5'	20'	11.11
STA 125+32.94	5'	20'	11.11
TOTAL			22.22

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70			
LOCATION		WIDTH (FT)	TON
STA 115+40.00	TO STA 117+05.00	20	30.8
STA 118+75.05	TO STA 125+32.94	20	122.81
TOTAL			153.61

BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)			
LOCATION		WIDTH (FT)	SQ YD
STA 116+99.00	TO STA 117+05.00	26'	17.55
STA 118+75.05	TO STA 118+81.05	26'	17.55
TOTAL			35.10

PAVEMENT REMOVAL			
LOCATION		WIDTH	SQ YD
STA 116+99.00	TO STA 117+63.60	18'	129.20
STA 118+16.45	TO STA 118+81.05	18'	129.20
TOTAL			258.40

HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH			
LOCATION		WIDTH	SQ YD
LT STA 115+40.00	TO STA 115+71.90	10'	35.44
LT STA 120+29.17	TO STA 125+32.94	10'	559.74
RT STA 115+40.00	TO STA 115+59.40	10'	21.56
RT STA 120+29.17	TO STA 125+32.94	10'	559.74
TOTAL			1,176.48

HOT-MIX ASPHALT SHOULDERS, 8"			
LOCATION		WIDTH (FT)	SQ YD
LT STA 115+40.00	TO STA 115+53.75	3'	4.58
LT STA 115+53.75	TO STA 115+59.75	3' TO 6'	3.00
LT STA 115+59.75	TO STA 117+05.00	6'	96.83
LT STA 118+75.05	TO STA 119+36.70	6'	41.1
LT STA 119+36.70	TO STA 119+39.80	6' TO 3'	1.55
LT STA 119+39.80	TO STA 125+32.94	3'	197.71
RT STA 115+40.00	TO STA 115+61.10	3'	7.03
RT STA 115+61.10	TO STA 115+79.10	3' TO 6'	9.00
RT STA 115+79.10	TO STA 117+05.00	6'	83.93
RT STA 118+75.05	TO STA 119+61.75	6'	57.8
RT STA 119+61.75	TO STA 119+79.75	6' TO 3'	9.00
RT STA 119+79.75	TO STA 125+32.94	3'	184.4
TOTAL			695.93

PIPE CULVERT REMOVAL	
LOCATION	FOOT
LT STA 124+86.00	18
TOTAL	18

PIPE CULVERT REMOVAL INCLUDES REMOVAL OF THE EXISTING CONCRETE HEADWALL

PIPE CULVERTS, CLASS D, TYPE 1 15"	
LOCATION	FOOT
LT STA 119+29.00	34
LT STA 119+86.00	40
LT STA 123+51.00	48
LT STA 124+86.00	44
TOTAL	166

PIPE DRAINS 4"	
LOCATION	FOOT
LT STA 117+34.00	17
RT STA 117+34.00	64
RT STA 118+46.00	35
TOTAL	116

END SECTION 15"	
LOCATION	EACH
LT STA 119+29.00	2
LT STA 119+86.00	2
LT STA 123+51.00	2
LT STA 124+86.00	2
TOTAL	8



JOB # 2223.5
 FILE NAME # *FILES*
 PLOT SCALE # *SCALE*
 PLOT DATE # *DATE*

DESIGNED - NAK
 DRAWN - TJD
 CHECKED - NAK
 DATE - 4/8/2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SBI RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1B	(12A)B-1	WABASH	52	12
CONTRACT NO. 74217				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				