

Designer Note: For use on urban projects where sidewalk removal and replacement required and access must be maintained at all times. There are pay items for Temporary Sidewalk and Temporary Ramps if the designer knows where and how much quantity will be needed. If using the pay items, provide locations and quantities in the plans and define the material to be used, but do not use this special provision.

TEMPORARY SIDEWALKS

Effective March 1, 1991

Revised February 1, 1996

Temporary sidewalks may be required at various locations as determined by the Engineer to provide access to and from businesses and to provide continuity for pedestrian traffic. The temporary sidewalks shall be constructed using material of the type and thickness as specified by the Engineer. The work, including the subsequent removal of the temporary sidewalk, will be paid for in accordance with Article 109.04 of the Standard Specifications.