

Designer Note: For use with small diameter culverts and box culverts. Discuss size/usage with your Project Engineer.

*List culvert location by Station, Size, and Description (temporary culvert or existing).

Example: Station 100+10 - 30" (750 mm) Temporary Culvert

FILLING EXISTING CULVERTS

Effective October 15, 1995

Revised January 1, 2007

This work shall consist of filling existing pipe culverts with controlled Low Strength Material meeting the requirements of Sections 593 and 1019 of the Standard Specifications.

The culverts to be filled are as follows:



The culverts shall be plugged on both ends with a plug material meeting the approval of the Engineer. The plug shall be adequate to withstand the hydrostatic load created during the filling operation. If the plugs fail during the filling operation, the Contractor shall be responsible for the cost of repairing the plugs and filling the remainder of the culvert.

This work, including the cost of plugging the pipe ends, will be paid for at the contract unit price Each for FILLING EXISTING CULVERTS. Each culvert location filled will be paid for separately.